

見 積 書

현대위아(주) 박지훈대리 貴下

견적일자	2016-12-26
견적번호	DD20160930
납 기	입하 2017년 9월
	최종검수 2017년 10월
견적유효기간	1개월
인도장소	멕시코 몬테레이
지불조건	귀사 지불 조건

대덕테크(주)



대표이사 : 배 태규

주소 : 울산광역시 울주군 청량면 화창9길 21

전화 : 052-273-3700

FAX : 052-258-0709

견적담당 : 대표 배태규

연락처 : 010-8540-1784

공사명 : 현대위아 멕시코 공장 CVJ POWDER COATING LINE 신설공사

견적금액: 一金 사억육천만원整 (₩460,000,000)

(VAT 별도)

NO	상세품목내역	수 량	단 가	금 액
1	WASHING IN-PUT C/V	1 LOT	4,520,000	4,520,000
2	IN-PUT 2 AXLE LOADER	1 LOT	13,050,000	13,050,000
3	WASHING BOOTH	1 LOT	48,705,000	48,705,000
4	SPRAY BOOTH	2 LOT	15,330,000	30,660,000
5	ROBOT	2 LOT	12,250,000	24,500,000
6	SAFETY FENCE	1 LOT	4,630,000	4,630,000
7	OVEN IN-PUT 정렬 C/V	1 LOT	4,300,000	4,300,000
8	OVEN IN-PUT PUSHER UNIT	1 LOT	3,940,000	3,940,000
9	OVEN	1 LOT	52,980,000	52,980,000
10	COOLING UNIT	1 LOT	1,690,000	1,690,000
11	OVEN OUT-PUT PULL UNIT	1 LOT	5,960,000	5,960,000
12	OVEN OUT-PUT 정렬 C/V	1 LOT	4,426,000	4,426,000
13	OUT-PUT 3 AXLE LOADER	1 LOT	17,400,000	17,400,000
14	STOCK CONVEYOR	1 LOT	10,436,000	10,436,000
15	전기(세척, 건조로)	2 SETS	76,013,000	76,013,000
16	OFF LINE TEST	1 LOT	14,100,000	14,100,000
17	포장 & F.O.B	5 C/T	3,920,000	3,920,000
18	현지설치작업	1 LOT	37,500,000	37,500,000
19	부대비용(항공권&체제비)	1 LOT	57,000,000	57,000,000
20	SPARE PARTS	1 LOT	10,000,000	10,000,000
직접비 합 계				425,730,000
20	일반관리비 & 기업이윤	10%		42,573,000
견적 합계				₩ 468,303,000

공개입찰가 (견적時 공란)

특
기
사
항

1. VAT 제외
2. 1차 UTILITY 공사 제외 (전기, 에어, 용수)
3. ROBOT BODY & CONTROLLER 사급 (ABB), GRIPPER & PLC 제어반은 견적포함
4. 약품 및 MASKING JIG SPARE 제외
5. 기타 견적사양외 내용 제외

DESCRIPTION	SPECIFICATION	MAT'L	Q'TY	UNIT	UNIT PRICE	AMOUNT	REMARK
1. WASHING LINE						66,275,000	
1-1. IN-PUT 정렬 CONVEYOR (W165×L1400×H950)							
1) CONVEYOR BODY	W165×L1400×H950	SUS304	1	LOT	600,000	600,000	
2) MOTOR	5RK90GU-AWMU+5GU180K	SUS304	1	SET	400,000	400,000	ORIENTAL
3) TT CHAIN	TT1143S	SUS304	3	M	70,000	210,000	한국체인
4) TT CHAIN SPROCKET	TT 60	SUS304	4	EA	130,000	520,000	가공
5) DRIVING SHAFT	Φ30 × 260L	S45C	1	EA	70,000	70,000	가공
6) IDLE SHAFT	Φ25 × 230L	S45C	1	EA	70,000	70,000	가공
7) IDLE ROLLER	Φ25 × 160L	S45C	2	EA	60,000	120,000	가공
8) DRIVING SPROCKET	RS40×B	S45C	2	EA	25,000	50,000	가공
9) MC ROLLER	Φ70 × 140L × B/L	MC	2	EA	65,000	130,000	가공
10) MC ROLLER	Φ70 × 60L × B/G	MC	1	EA	70,000	70,000	가공
11) LASER & BENDING			1	LOT	120,000	120,000	가공
12) 잡자재 및 소모품	B/G 외		1	LOT	180,000	180,000	
13) 제작인건비	3인×5일		15	M/D	120,000	1,800,000	
14) PAINTING	분체도장		1	LOT	180,000	180,000	
SUB TOTAL						4,520,000	
1-2. IN-PUT 2 AXLE LOADER (W410×L1340×H2,000)							
1) LOADER FRAME	SQ 200×150	SS400	1	LOT	900,000	900,000	
2) X AXLE DRIVE UNIT	MY3M40-800		1	SET	1,000,000	1,000,000	SMC
3) Y AXLE DRIVE UNIT	CDAF63-300		1	SET	600,000	600,000	SMC
4) AIR CHUCK	11-MHL2-25D		2	SET	600,000	1,200,000	SMC
5) GUIDE TRACK	Φ30 × 800L	SUJ	1	SET	1,200,000	1,200,000	가공
6) L/M GUIDE	SL30UU+SR30W	SUS304	1	SET	900,000	900,000	THK
7) GRIPPER JIG	1 FINGER	SUJ	1	SET	1,400,000	1,400,000	가공
8) GRIPPER UNIT	SOL 4연식		1	SET	1,000,000	1,000,000	SMC
9) LASER & BENDING			1	LOT	500,000	500,000	
10) 잡자재 및 소모품	B/G 외		1	LOT	500,000	500,000	
11) 제작인건비	3인×8일		25	M/D	140,000	3,500,000	
12) PAINTING	분체도장		1	LOT	350,000	350,000	
SUB TOTAL						13,050,000	
1-3. WASHING BOOTH (W1,400×L4,200×H1,600)							
1) CASING FRAME	SQ 50×50외	SUS304	1	LOT	4,200,000	4,200,000	제작품
2) CASING	PLATE 2t	SUS304	1	LOT	2,600,000	2,600,000	제작품
3) MOTOR&REDUCER	DWBM80×1/600		1	SET	1,800,000	1,800,000	삼양
4) MESH BELT CHAIN	1"×1" × (W 21")		12	M	320,000	3,840,000	KEYSTONE
5) SPROCKET	1"×1" × 23NT	S45C	8	EA	80,000	640,000	가공
6) TORQUE LIMIT	TL-10-12	S45C	1	SET	500,000	500,000	가공
7) DRIVING SHAFT	Φ40×700L	S45C	1	SET	300,000	300,000	가공
8) IDLE SHAFT	Φ40×600L	S45C	1	SET	250,000	250,000	가공
9) TAKE UP	Φ50×600L + TENSION	S45C	1	SET	250,000	250,000	가공
10) DEGREASING TANK	PLATE 3t	SUS304	1	LOT	1,800,000	1,800,000	제작품
11) HOT RINSE TANK	PLATE 3t	SUS304	1	LOT	1,000,000	1,000,000	제작품
12) TANK 보온	GLASSWOOL 50t	G/W	1	LOT	300,000	300,000	벽산
13) 보온재 COVER	PLATE 1.6t	EGI	1	LOT	600,000	600,000	제작품

DESCRIPTION	SPECIFICATION	MAT'L	Q'TY	UNIT	UNIT PRICE	AMOUNT	REMARK
14) OVER FLOW	PLATE 3t + 40A	SUS304	1	LOT	300,000	300,000	제작품
15) DRAIN & PUMP	50A	SUS304	1	LOT	800,000	800,000	제작품
16) MESH FILTER	#40 300×300×20t	SUS304	1	SET	400,000	400,000	제작품
17) SPRAY PIPING	25A + 보온	SUS304	1	LOT	800,000	800,000	제작품
18) SPRAY NOZZLE	FULL CONE 1/4" 8ℓ/min	SUS304	65	EA	13,000	845,000	SPRAY SYSTEM
19) HEATER	TUBE 10kw - 1,000mmL	SUS304	6	EA	50,000	300,000	동우히터
20) 탈지 순환 PUMP	MTR8-2/2 × 1.1kw		1	SET	1,500,000	1,500,000	GRUNDFOS
20) 탈지 SPRAY PUMP	MTR15-2/2× 3kw		1	SET	2,500,000	2,500,000	GRUNDFOS
21) OIL SKIMER	BELT TYPE / S8125GS-T	SUS304	1	SET	1,600,000	1,600,000	제작품
22) 탕세 SPRAY PUMP	MTR8-2/2 × 1.1kw		1	SET	1,300,000	1,300,000	GRUNDFOS
23) AIR BLOW NOZZLE	193ℓ/min	P.P	40	EA	8,000	320,000	SPRAY SYSTEM
24) SOL VALVE	25A	SUS304	4	SET	140,000	560,000	
25) DRY HEATER	10,000 "S" 13kw		1	SET	1,400,000	1,400,000	LEISTER
26) RING BLOWER	629 3.7kw		1	SET	1,000,000	1,000,000	HAESUNG
27) MIST CLEALER	UCK5-DLH	SUS304	1	LOT	3,000,000	3,000,000	REVEN
28) EXHAUST DUCT	125A~200A PIPE	SUS304	1	LOT	1,300,000	1,300,000	제작품
29) DAMPER	125A	SUS304	4	EA	100,000	400,000	제작품
30) LASER & BENDING			1	LOT	1,600,000	1,600,000	가공
31) 잡자재 및 소모품	UCP B/G, FITTING류 외		1	LOT	1,200,000	1,200,000	
32) 제작인건비	3인×25일		75	M/D	100,000	7,500,000	
33) PAINTING	분체도장		1	LOT	2,000,000	2,000,000	
SUB TOTAL						48,705,000	

2. POWER COATING BOOTH LINE

59,790,000

2-1. SPRAY BOOTH (W1,150×L850×H2,100) - 2 SETS

1) FRAME & CASING	W1,150×L850×H2,100	SUS304	2	LOT	1,300,000	2,600,000	제작품
2) WALKWAY	W1,000×L1,700	SS400	1	SET	800,000	800,000	제작품
3) TURNNING MOTOR	5RK90GU-AMU+50GU15K		4	SET	250,000	1,000,000	ORIENTAL
4) TURNNING BASE	W500×L300×8t	SS400	2	EA	100,000	200,000	제작품
5) TURNNING HOUSING	Φ130×L180	SS400	4	EA	160,000	640,000	제작품
6) TURNNING HOLDER		SS400	4	EA	200,000	800,000	제작품
7) TURNNING FIX NUT		SS400	4	EA	50,000	200,000	제작품
8) COUPLING	AL-SDWA-39C		4	EA	40,000	160,000	KS
9) MASKING PLATE	W120×L330×10t	SUJ2	2	EA	90,000	180,000	제작품
10) MASKING CYLINDER	SMC - 63 - 300ST		2	EA	180,000	360,000	SMC
11) MASKING BODY	Φ135×L125	M.C	4	EA	60,000	240,000	가공
12) MASKING CAP	Φ135×L30	M.C	4	EA	50,000	200,000	가공
13) MASKING JOINT	Φ112×L75	M.C	4	EA	60,000	240,000	가공
14) MASKING BUSHING	Φ75×L16	M.C	8	EA	40,000	320,000	가공
15) GUIDE BAR	Φ25×L610	SUJ2	4	EA	60,000	240,000	가공
16) EXHAUST FAN	27CMM×205mmAq×0.6kw		2	EA	300,000	600,000	제작품
17) CARTRIDGE FILTER	Φ270×L600		4	EA	50,000	200,000	조일기계
18) PULSE NOZZLE	20A		4	EA	60,000	240,000	조일기계
19) PULSE VALVE	20A		4	EA	60,000	240,000	조일기계
20) POWERDER GUN	PEA-C3		4	SET	3,000,000	12,000,000	WAGNER
21) AIR UNIT	SOL 5연식		2	SET	1,000,000	2,000,000	SMC

DESCRIPTION	SPECIFICATION	MAT'L	Q'TY	UNIT	UNIT PRICE	AMOUNT	REMARK
22) LASER & BENDING			2	LOT	500,000	1,000,000	가공
23) 잡자재 및 소모품	B/G 외		1	LOT	300,000	300,000	
24) 제작인건비	3인×15일		45	M/D	100,000	4,500,000	
25) PAINTING	분체도장		2	LOT	700,000	1,400,000	
SUB TOTAL						30,660,000	
2-2. ROBOT - 2 SETS							
1) ROBOT BODY	IRB 4600-60/IRC5-AXIS 6		2	SET	위아사급		ABB
2) ROBOT CONTROLLER	IRC 5		2	SET	위아사급		ABB
3) ROBOT GRIPPER	2 FINGER CLAMP		2	SET	2,900,000	5,800,000	제작품
	파지 GRIPPER		2	SET	800,000	1,600,000	
4) SOL BLOCK	D-NET 통신		2	SET	1,400,000	2,800,000	SMC
5) HOSE , CABLE BRKT		AL	2	SET	300,000	600,000	제작품
6) AIR HOSE & FITTING		SUS304	1	LOT	1,400,000	1,400,000	구매품
7) ROBOT 조립	3인×10일		30	M/D	120,000	3,600,000	
8) ROBOT TEACHING	3인×15일		45	M/D	100,000	4,500,000	
9) ROBOT 현지설치	3인×10일		30	M/D	140,000	4,200,000	
SUB TOTAL						24,500,000	
2-3. SAFETY FENCE							
1) PARTITION	1,000W × 2,000H		15	EA	250,000	3,750,000	제작품
2) DOOR	1,000W × 2,000H		2	EA	300,000	600,000	제작품
3) SAFETY CONNECTOR			2	SET	70,000	140,000	
4) 잡자재 및 소모품			1	LOT	140,000	140,000	
SUB TOTAL						4,630,000	
3. OVEN LINE						101,132,000	
3-1. IN-PUT 정렬 CONVEYOR (W165×L1880×H950)							
1) CONVEYOR BODY	W165×L1400×H950	SUS304	1	LOT	500,000	500,000	
2) MOTOR	5RK90GU-AWMU+5GU180K	SUS304	1	SET	300,000	300,000	ORIENTAL
3) TT CHAIN	TT1143S	SUS304	4	M	40,000	160,000	한국체인
4) TT CHAIN SPROCKET	TT 60	SUS304	4	EA	120,000	480,000	가공
5) DRIVING SHAFT	Φ30 × 260L	S45C	1	EA	50,000	50,000	가공
6) IDLE SHAFT	Φ25 × 230L	S45C	1	EA	50,000	50,000	가공
7) IDLE ROLLER	Φ25 × 160L	S45C	2	EA	50,000	100,000	가공
8) DRIVING SPROCKET	RS40×B	S45C	2	EA	20,000	40,000	가공
9) MC ROLLER	Φ70 × 140L × B/L	MC	2	EA	60,000	120,000	가공
10) MC ROLLER	Φ70 × 60L × B/G	MC	1	EA	40,000	40,000	가공
11) LASER & BENDING			1	LOT	210,000	210,000	가공
12) 잡자재 및 소모품	B/G 외		1	LOT	250,000	250,000	
13) 제작인건비	3인×5일		15	M/D	120,000	1,800,000	
14) PAINTING	분체도장		1	LOT	200,000	200,000	
SUB TOTAL						4,300,000	
3-2. IN-PUT PUSHER UNIT (W,1000×L485×H950 - 350ST)							
1) FRAME & LEG	W,1000×L485×H950	SS400	1	LOT	300,000	300,000	
2) AIR CYLINDER	MY1CW32-350ST		1	SET	800,000	800,000	SMC
3) HOLDING JIG	W,1000 × 8 CIRCLE	M.C	1	LOT	1,200,000	1,200,000	가공

DESCRIPTION	SPECIFICATION	MAT'L	Q'TY	UNIT	UNIT PRICE	AMOUNT	REMARK
4) LASER & BENDING			1	LOT	130,000	130,000	가공
5) 잡자재 및 소모품	B/G 외		1	LOT	130,000	130,000	
6) 제작인건비	3인×4일		12	M/D	100,000	1,200,000	
7) PAINTING	분체도장		1	LOT	180,000	180,000	
SUB TOTAL						3,940,000	
3-3. OVEN (W1,730×L4,400×H1,800)							
1) FRAME & LEG	W1,730×L4,400×H1,800	SS400	1	LOT	2,800,000	2,800,000	
	L65×65×6t	SS400	1	LOT	300,000	300,000	
	L50×50×6t	SS400	1	LOT	350,000	350,000	
2) CASING	PLATE 3t	SUS304	1	LOT	3,000,000	3,000,000	
	PLATE 1.5t	EGI	1	LOT	2,000,000	2,000,000	
3) INSULATION	R/W 150t #80	R/W	1	LOT	1,400,000	1,400,000	
4) INSPECTION DOOR		SUS304	3	SET	300,000	900,000	
5) GEARD MOTOR	DWBM120 × 1/30		1	SET	500,000	500,000	삼양
6) REDUCER	DWD100 × 1/600		1	SET	800,000	800,000	삼양
7) FLAT WIRE CHAIN	1"×1" × (W 53")		15	M	800,000	12,000,000	KYSTONE
8) SPROCKET	P25.4 × 23NT - B/R	S45C	18	EA	150,000	2,700,000	가공
9) MC ROLLER	Φ172.8 × Φ60 × L200	M.C	6	EA	150,000	900,000	가공
10) TORQUE LIMIT	TL-700-2	S45C	1	EA	500,000	500,000	가공
11) DRIVE SHAFT	Φ60 × L1,700	S45C	1	EA	250,000	250,000	가공
12) IDLE SHAFT	Φ50 × L1,700	S45C	6	EA	180,000	1,080,000	가공
13) TUBE HEATER	1.25kW - 1,400L U	SUS304	15	EA	60,000	900,000	동우히터
14) TURBO FAN	80CMM×80mmAq×5HP	SUS304	1	SET	2,600,000	2,600,000	제작품
15) R.C FAN	30CMM×35mmAq×1.5HP	SUS304	3	SET	1,800,000	5,400,000	제작품
16) EXHAUST HOOD	W1,730×H400	SUS304	2	SET	300,000	600,000	제작품
17) SPIRAL DUCT	250A		30	M	30,000	900,000	구매품
18) LASER & BENDING			1	LOT	1,500,000	1,500,000	가공
19) 잡자재 및 소모품	B/G 외		1	LOT	600,000	600,000	
20) 제작인건비	4인×20일		80	M/D	100,000	8,000,000	
21) PAINTING	분체도장		1	LOT	3,000,000	3,000,000	
SUB TOTAL						52,980,000	
3-4. COOLING UNIT (W,1300×L490×H350)							
1) FRAME & LEG	W,1300×L490×H350	SUS304	1	LOT	250,000	250,000	
2) COOLING BLOWER	DR-DF25ASB		3	SET	60,000	180,000	제작품
3) LASER & BENDING			1	LOT	60,000	60,000	가공
4) 잡자재 및 소모품	B/G 외		1	LOT	60,000	60,000	
5) 제작인건비	2인×3일		9	M/D	120,000	1,080,000	
6) PAINTING	분체도장		1	LOT	60,000	60,000	
SUB TOTAL						1,690,000	
3-5. OUT-PUT PULL UNIT (W,1120×L920×H950 - 350ST)							
1) FRAME & LEG	W,1120×L920×H950	SS400	1	LOT	400,000	400,000	
2) AIR CYLINDER	MY1CW32-350ST		1	SET	700,000	700,000	SMC
3) MAGNETIC	33 × 80 DC110V		8	SET	300,000	2,400,000	
4) LASER & BENDING			1	LOT	250,000	250,000	가공
5) 잡자재 및 소모품	B/G 외		1	LOT	350,000	350,000	
6) 제작인건비	3인×4일		12	M/D	140,000	1,680,000	

DESCRIPTION	SPECIFICATION	MAT'L	Q'TY	UNIT	UNIT PRICE	AMOUNT	REMARK
7) PAINTING	분체도장		1	LOT	180,000	180,000	
SUB TOTAL						5,960,000	
3-6. OVEN OUT-PUT 정렬 CONVEYOR (W165×L1980×H950)							
1) CONVEYOR BODY	W165×L1400×H950	SUS304	1	LOT	500,000	500,000	
2) MOTOR	5RK90GU-AWMU+5GU180K	SUS304	1	SET	400,000	400,000	ORIENTAL
3) TT CHAIN	TT1143S	SUS304	4	M	40,000	160,000	한국체인
4) TT CHAIN SPROCKET	TT 60	SUS304	4	EA	140,000	560,000	가공
5) DRIVING SHAFT	Φ30 × 260L	S45C	1	EA	60,000	60,000	가공
6) IDLE SHAFT	Φ25 × 230L	S45C	1	EA	60,000	60,000	가공
7) IDLE ROLLER	Φ25 × 160L	S45C	2	EA	50,000	100,000	가공
8) DRIVING SPROCKET	RS40×B	S45C	2	EA	18,000	36,000	가공
9) MC ROLLER	Φ70 × 140L × B/L	MC	2	EA	60,000	120,000	가공
10) MC ROLLER	Φ70 × 60L × B/G	MC	1	EA	40,000	40,000	가공
11) LASER & BENDING			1	LOT	160,000	160,000	가공
12) 잡자재 및 소모품	B/G 외		1	LOT	250,000	250,000	
13) 제작인건비	3인×5일		15	M/D	120,000	1,800,000	
14) PAINTING	분체도장		1	LOT	180,000	180,000	
SUB TOTAL						4,426,000	
3-7. OUT-PUT 3 AXLE LOADER (W1,100×L1,400×H2,000)							
1) LOADER FRAME	SQ 200×150	SS400	1	LOT	1,200,000	1,200,000	
2) X AXLE DRIVE UNIT	MY3M40-1000		1	SET	1,500,000	1,500,000	SMC
3) Y AXLE DRIVE UNIT	MY3M40-800		1	SET	1,400,000	1,400,000	SMC
4) Z AXLE DRIVE UNIT	CDAF63-300		1	SET	400,000	400,000	SMC
5) AIR CHUCK	11-MHL2-25D		4	SET	500,000	2,000,000	SMC
6) GUIDE TRACK	Φ30 × 1,000L,800L	SUJ	2	SET	1,000,000	2,000,000	가공
7) L/M GUIDE	SL30UU+SR30W	SUS304	2	SET	800,000	1,600,000	THK
8) GRIPPER JIG	2 FINGER	SUJ	1	SET	1,800,000	1,800,000	가공
8) GRIPPER UNIT	SOL 4연식		1	SET	800,000	800,000	SMC
9) LASER & BENDING			1	LOT	400,000	400,000	
10) 잡자재 및 소모품	B/G 외		1	LOT	400,000	400,000	
11) 제작인건비	3인×10일		30	M/D	120,000	3,600,000	
12) PAINTING	분체도장		1	LOT	300,000	300,000	
SUB TOTAL						17,400,000	
3-8. STOCK CONVEYOR (W710×L1800×H950)							
1) FRAME & LEG	W710×L1800×H950	SS400	1	LOT	1,800,000	1,800,000	
2) MOTOR	DWBM80×1/600		1	SET	700,000	700,000	
3) TT CHAIN	TT1143S×6열	SUS304	25	M	50,000	1,250,000	한국체인
4) TT CHAIN SPROCKET	TT 60	SUS304	12	EA	140,000	1,680,000	가공
5) DRIVING SHAFT	Φ50 × 800L	S45C	1	EA	60,000	60,000	가공
6) IDLE SHAFT	Φ40 × 700L	S45C	1	EA	50,000	50,000	가공
7) IDLE ROLLER	Φ25 × 160L	S45C	24	EA	40,000	960,000	가공
8) DRIVING SPROCKET	RS40×B	S45C	2	EA	18,000	36,000	가공
9) MC ROLLER	Φ70 × 140L × B/L	MC	6	EA	50,000	300,000	가공
10) MC ROLLER	Φ70 × 60L × B/G	MC	10	EA	40,000	400,000	가공
11) LASER & BENDING			1	LOT	300,000	300,000	가공
12) 잡자재 및 소모품	B/G 외		1	LOT	400,000	400,000	

DESCRIPTION	SPECIFICATION	MAT'L	Q'TY	UNIT	UNIT PRICE	AMOUNT	REMARK
13) 제작인건비	3인×5일		15	M/D	140,000	2,100,000	
14) PAINTING	분체도장		1	LOT	400,000	400,000	
SUB TOTAL						10,436,000	
기계장치 합계						227,197,000	

4. 전기

4-1. WASHING CONTROL PANEL

1) MCCB	3VL4725-1DC36-0AA0(20~150A)	21 EA	200,000	4,200,000	SIEMENS
	5SY5210-7, 202-7	8 EA	50,000	400,000	SIEMENS
2) M.G S/W	3RT2024,26,28-1AP04	24 EA	25,000	600,000	SIEMENS
3) EOCR	3BZ2	23 EA	100,000	2,300,000	SCHNEIDER
4) CT	200/5VA	4 EA	8,000	32,000	
5) TRANSFORMER	480/220/110V 5KVA	1 EA	700,000	700,000	SIEMENS
6) TIC	E5CC-C03ASM-002	3 EA	70,000	210,000	OMRON
7) PLC	SIEMENS S-7	2 EA	5,000,000	10,000,000	SIEMENS
8) I/O BOARD	R32ST	1 EA	250,000	250,000	
9) NOISER FILTER	10A	1 EA	30,000	30,000	MURR
10) POWER SUPPLY	DC 24V 10A	1 EA	300,000	300,000	OMRON
11) I/O CABLE	2M	10 EA	25,000	250,000	
12) TOUCH SCREEN	6AV2124-OMC01-OAX0	2 EA	1,800,000	3,600,000	SIEMENS
13) PT	480/110V	1 EA	80,000	80,000	
14) RELAY	MY-4N 110V	30 EA	5,000	150,000	HONEYWELL
15) MULTI METER	KDA-A	1 EA	300,000	300,000	LIGHT STAR
16) INVERTER	6SE6420-2UD21-5AA1	3 EA	700,000	2,100,000	SIEMENS
17) A-METER	KAA-08 400A 300%	3 EA	18,000	54,000	
18) WH-METER	OMNI-3315	1 EA	180,000	180,000	
19) METER	MP5W	1 EA	60,000	60,000	
20) SURGE FILTER	BJLPA3P-LCD DISPLAY TYPE	1 EA	2,000,000	2,000,000	BJ TECH
21) SPARKER KILLER	K3CR-50500	26 EA	6,000	156,000	KEM
22) PATROL LAMP	ST56LBZ32 4RYG SZ24	2 EA	80,000	160,000	Q-LIGHT
23) SWITCH	KH-506	1 LOT	400,000	400,000	KOINO
24) PANEL AIRCON	AP-ES140	1 EA	1,800,000	1,800,000	AIR MAJOR
25) 조립용 자재		1 LOT	700,000	700,000	
26) MAIN PANEL외함	1800*2000*500	1 EA	1,500,000	1,500,000	RITTAL형
27) LOCAL BOX	400*650	2 EA	300,000	600,000	RITTAL형
28) 제작, 조립 인건비	3인×10일	30 M/D	100,000	3,000,000	
SUB TOTAL				36,112,000	

4-2. OVEN CONTROL PANEL

1) MCCB	3VL4725-1DC36-0AA0(20~150A)	14	EA	300,000	4,200,000	SIEMENS
	5SY5210-7, 202-7	7	EA	50,000	350,000	SIEMENS
2) M.G S/W	3RT2024,26,28-1AP04	10	EA	30,000	300,000	SIEMENS
3) EOCR	3BZ2	9	EA	110,000	990,000	SCHNEIDER
4) CT	200/5VA	7	EA	7,000	49,000	
5) TRANSFORMER	480/220/110V 5KVA	1	EA	700,000	700,000	SIEMENS
6) TIC	E5CC-C03ASM-002	3	EA	70,000	210,000	OMRON
7) PLC	SIEMENS S-7	1	EA	4,500,000	4,500,000	SIEMENS

DESCRIPTION	SPECIFICATION	MAT'L	Q'TY	UNIT	UNIT PRICE	AMOUNT	REMARK
8) I/O BOARD	R32ST		1	EA	250,000	250,000	
9) NOISER FILTER	10A		1	EA	30,000	30,000	MURR
10) POWER SUPPLY	DC 24V 10A		1	EA	300,000	300,000	OMRON
11) I/O CABLE	2M		10	EA	25,000	250,000	
12) TOUCH SCREEN	6AV2124-OMC01-OAX0		1	EA	1,800,000	1,800,000	SIEMENS
13) SCR UNIT	480V 35A		2	EA	500,000	1,000,000	HAN YOUNG
14) PT	480/110V		1	EA	80,000	80,000	
15) RELAY	MY-4N 110V		20	EA	5,000	100,000	HONEYWELL
16) MULTI METER	KDA-A		1	EA	250,000	250,000	LIGHT STAR
17) INVERTER	6SE6420-2UD21-5AA1		3	EA	700,000	2,100,000	SIEMENS
18) A-METER	KAA-08 400A 300%		3	EA	18,000	54,000	
19) WH-METER	OMNI-3315		1	EA	180,000	180,000	
20) METER	MP5W		1	EA	60,000	60,000	
21) SURGE FILTER	BJLPA3P-LCD DISPLAY TYPE		1	EA	2,500,000	2,500,000	BJ TECH
22) SPARKER KILLER	K3CR-50500		8	EA	6,000	48,000	KEM
23) NOISER FILTER	ZNC2210-00U		5	EA	30,000	150,000	TDK
24) PATROL LAMP	ST56LBZ32 4RYG SZ24		2	EA	80,000	160,000	Q-LIGHT
25) SWITCH	KH-506		1	LOT	400,000	400,000	KOINO
26) PANEL AIRCON	AP-ES140		1	EA	1,800,000	1,800,000	AIR MAJOR
27) 조립용 자재			1	LOT	600,000	600,000	
28) MAIN PANEL외함	1800*2000*500		1	EA	1,500,000	1,500,000	RITTAL형
29) LOCAL BOX	400*650		1	EA	300,000	300,000	RITTAL형
30) 제작, 조립 인건비	3인×8일		25	M/D	120,000	3,000,000	
SUB TOTAL						28,211,000	

4-3. 설치자재 및 인건비

1) CABLE	LAPP 4G 25SQ 외		1	LOT	2,500,000	2,500,000	LAPP CABLE
2) HEATING CABLE	16SQ		1	LOT	300,000	300,000	
3) CABLE DUCT	200*100		1	LOT	1,400,000	1,400,000	
4) SENSOR	BES Q40KFU-NAC25F-S04G		3	EA	30,000	90,000	BALLUFF
	BES 516-361-E5-Y-S4		25	EA	30,000	750,000	BALLUFF
	BOS 6K-NU-LK10-S75		11	EA	110,000	1,210,000	BALLUFF
	BOS 6K-PU-RD10-S75		1	EA	150,000	150,000	BALLUFF
5) SENSOR CABLE	M12 CONNECTOR 3M		40	EA	13,000	520,000	
6) DOOR SAFET SENSOR	MGB-PN		3	EA	400,000	1,200,000	EUCHNER
7) TIC SENSOR	PT100		6	EA	70,000	420,000	
8) RECODER	GR-200		1	SET	1,400,000	1,400,000	
9) MAGNETIC CONTROL	KMS-20		1	SET	500,000	500,000	
10) FLEXIBLE	28MM 외		1	LOT	400,000	400,000	
11) 전선관	28MM 외		1	LOT	250,000	250,000	
12) 설치잡자재	CHANNEL 외		1	LOT	600,000	600,000	
SUB TOTAL						11,690,000	

전기장치 합계

76,013,000

5. OFF LINE TEST

1) OLT 설치	기계 4	15	M/D	140,000	2,100,000	
	전기 2	10	M/D	140,000	1,400,000	

DESCRIPTION	SPECIFICATION	MAT'L	Q'TY	UNIT	UNIT PRICE	AMOUNT	REMARK
2) 장비비			5	대	300000	1,500,000	
3) PROGRAM & TEST	기계 2		15	M/D	140,000	2,100,000	
	전기 2		20	M/D	140,000	2,800,000	
4) 해체 작업	기계 4		15	M/D	140,000	2,100,000	
	전기 2		15	M/D	140,000	2,100,000	
OLT 합계						14,100,000	
6. 포장 & F.O.B							
1) 포장	WOOD BOX		4	C/T	800,000	3,200,000	
2) F.O.B 부산			4	C/T	180,000	720,000	
포장 & F.O.B 합계						3,920,000	
7. 현지 설치작업							
1) 컨테이너 해포 및 운반	5 CONTAINER		15	M/D	300,000	4,500,000	장비 위아지원
2) 기계 설치	기계 3인×10일		30	M/D	300,000	9,000,000	장비 위아지원
	전기 2인×10일		20	M/D	300,000	6,000,000	
4) 시운전	기계 2인×10일		20	M/D	300,000	6,000,000	
	전기 2인×10일		20	M/D	300,000	6,000,000	
5) 양산대기	기계 1, 전기 1		20	M/D	300,000	6,000,000	
현지 설치작업 합계			125			37,500,000	
8. 항공권 및 체제비							
1) 항공권	서울 - > 몬테레이		8	회	3,000,000	24,000,000	
2) 현지 체제비	숙박 & 식대		150	M/D	200,000	30,000,000	
3) DOCUMENTS			1	LOT	3,000,000	3,000,000	
항공권 및 체제비 합계						57,000,000	