

JTEKT CORPORATION

Kariya Plant : 1, Asahimachi 1-chome, Kariya, Aichi-pref., Japan
TEL : 81-566-25-5170 - 5174 FAX : 81-566-25-5470



Messrs. HYUNDAI WIA CORPORATION
KOREA

Date : Oct. 31, 2016

ESTIMATE

No. YH -161031-1

ENQUIRER : NILL

REF. NO. : NILL

MACHINE : TOYODA CNC Production Anguler - Wheel slide Cylindrical Grinder
model GL5Ai-63

- as per attached brochure and/or our technical Specifications
No. VP-XXXXX

PRICE : F.O.B. Nagoya Port in Japanese Yen
- details as per attached sheets -

DELIVERY : PLACE : Nagoya Port

TIME : 6-7 months after our receipt of your order note

PAYMENT : Draft at sight under an irrevocable L/C to be established in favour of
TOYOTA TSUSHO CORPORATION, Nagoya, Japan

VALIDITY : 1 months after the date of this Estimate, or by the date of _____

We are much pleased in quoting you herein, and thanking for your valued orderin advance.

Yours faithfully,
ASIA REGIONAL SALES DEPT.

K. Nakagawa
Manager

JTEKT CORPORATION

[A] TOYODA CNC Angular-Wheelslide Cylindrical Grinder model 60M GL5Ai-63 (wheel dia. of 610 mm Specification)

* Specially designed and tooled up for
finish-grinding of OUTER RACE

* Our specification No.HM18267

1	<u>Basic Machine</u>		
1.1	Basic machine model 60M GL5Ai-63	1 set	25,170,000
2	<u>Extra Equipment:</u>		
2.1	Machine bed	1 set	IIBM
2.2	One-body type table	1 set	IIBM
2.3	Live spindle workhead	1 set	519,000
2.4	Footstock, automatic reposition type, manual taper adjustment type	1 set	960,000
2.5	Rotary diamond roll type wheel dresser, mounted on the rear of workhead with the inverter	1 set	909,000
2.6	Hydraulic pump unit, common with low oil level warning switch	1 set	IIBM
2.7	Lubricating and operating oil pump unit common with low oil level warning switch	1 set	IIBM
2.9	Cyclone type coolant supply equipment with magnetic separator (240 L/min.) and ,bed cleaning pump, piping for cleaning bed, coolant cooler and sludge box and cyclone filter	1 set	3,453,000
2.10	FANUC-make CNC unit (FANUC 0i)	1 set	IIBM
2.11	Standard service tool kit	1 set	IIBM
2.12	Machine painting (RAL 7035, 1018)	1 set	IIBM
2.13	Design fee for Additional workpieses	5 pcs.	1,069,000
2.14	Manual overhead open/shut type full cover and totally-closed cover	1 set	1,198,000
2.15	Gentry loader	1 lot	¥13,317,000
Sub Total: [1]			¥46,595,000

3 OPTIONAL ACCESSORIES

3.1	Automatic electric in-process gauging system, with 1 pce. of "MARPOSS "-make table-mounted type hydraulically-operated gauging head and control unit , pipings, wirings and fittings (UNIMAR S10, AMP P1), including automatic lateral locator(UNIMAR W26, AMP P1C), mounted on table	1 set	3,072,000
3.2	Maser bar (for spindle)	1 set	85,000
3.3	3-steps signal tower with buzzer	1 set	71,000
3.4	Cooler for electric control box (RITTAL)	1 set	431,000

3.5	Local lighting unit	1 set	77,000
	Lighting units inside control box	1 set	77,000
3.6	Electric type jib crane	1 set	590,000
3.7	Air gun & coolant gun	1 pce.	71,000
3.8	Mist collector attaching arrangement (excluding mist collector)	1 set	103,000
3.9	Terminal box between loader and machine	1 set	90,000
3.10	Wheel guard auto offset device	1 set	282,000
3.11	Gap eliminator for wheel feed	1 set	335,000
3.12	Wheel balance unit(FT1300H,E78)	1 set	848,000
3.13	Wheel balancing stand including balance arbor	1 set	223,000
Sub Total: [3]			¥6,355,000
4	<u>Durable tool:</u>		
4.1	Grinding wheel flange	6 sets	¥1,767,000
4.2	Feeler & contact for auto-locator	2 sets	108,000
4.3	Feeler & contact for auto-sizer	2 sets	200,000
4.4	Special type work driving center (L-side only)	2 sets	295,000
4.5	Carbide-tipped work center(R-side only)	2 sets	64,000
4.6	Driving plate(for attaching drive center)	10 sets	512,000
4.7	Loader Jaw	6 sets	392,000
4.8	Grinding wheel	6 pcs.	¥461,000
4.9	Diamond roll, (1 pcs. as spare)	2 pcs.	397,000
Sub Total: [4]			¥4,196,000
5	<u>Supervisor fee:</u>		
5.1	Trial at setup place(MEXICO)	1 lot	¥2,500,000
5.2	FOB delivery (include packing)		IIBM
Sub Total: [5]			¥2,500,000
6	<u>Training & Producton support fee:</u>		
6.1	Training(operate & maintence)	1 lot	¥1,500,000
6.2	Production Support	1 lot	¥2,000,000
Sub Total: [6]			¥3,500,000
7	<u>Spare parts</u>		
7.1	Spare parts (3% of Basic machine)	1 lot	¥1,000,000
Sub Total: [7]			¥1,000,000

8 optional items

8.1	Foundation bar collet type	1 set	¥163,000
8.3	Work existing confirmation device(monosasikun)	1 set	192,000
Sub Total: [8]			¥355,000
GRAND TOTAL: F.O.B. Nagoya port [A]			¥64,501,000