

견 적 서

REF NO. : PBQ-17017-2

현대위아 주식회사 귀중

2017년 04월 04일 (화)

하기품목의 조회에 진심으로 감사드리며, 다음과 같이 견적하오니 검토하여 주시기바랍니다.

-다 음-

(단위: 원)

No	구 분	수량	단가	금액	비 고
적용WORK : FORD CX 483_23025-C4902 / C4912(CT:40sec)					
1	초음파탐상기(Ultrasonic Test M/C)	1식	₩320,360,000	₩320,360,000	5축
2	포장(WOODEN PACKING CHG) & 운송	1식	₩5,000,000	₩5,000,000	FOB BUSAN
FOB 합계				₩325,360,000	
3	설치/시운전/교육 (Install/Try-Out) 1, 2차, 양산	1식	₩70,645,300	₩70,645,300	MEXICO
총 합계				₩396,005,300	
최종금액				₩396,000,000	천단위 절사

특기사항

- 1 인도조건 : FOB BUSAN
- 2 납기 : 주문접수후 180일
- 3 결제조건 : 계약금 10%, 중도금(BL 발행시) 60%, 1차설치 완료후 10%, 잔금(FAC발행시) 20%
- 4 상기단가의 상세는 "**별지**"를 참조하시기바랍니다.
- 5 제작사양/범위
 - 1) CT 사양 : 40SEC
 - 2) 상기설비의 제작조건 및 기기사용에 대해서는 합의의 제작사양을 기준으로합니다.
 - 3) 상기 금액은 "OUT STOCKER UNIT"포함 입니다.
 - 4) 상기 금액은 "현지 통역, 스페인어메뉴얼, UL인증" 포함입니다.
- 6 제출서류(검사성적서)
 - 1) 설비취급설명서 4부(스페인어 & 영어)
- 7 UL인증필
- 8 견적 유효기간 : 30일.
- 9 V. A. T 별도.

주식회사 피앤에스 대표이사 박 봉 수



1.초음파 검사기(UST)

(単位:KRW)

NO	구분	규격/형식	수량	단위	단가	금액	비고
1	FRAME						
1.1	Frame unit		1	SET	₩20,000,000	₩20,000,000	
1.2	All Fance Cover		1	SET	₩11,000,000	₩11,000,000	
1.3	Jig Unit		1	SET	₩6,000,000	₩6,000,000	
1.4	UT Master Work		2	SET	₩2,000,000	₩4,000,000	
2	LOADER						
2.1	Ball Screw Type		1	SET	₩23,000,000	₩23,000,000	2축
2.2	Chuck Unit		2	SET	₩1,000,000	₩2,000,000	
3	UST UNIT & UT TANK						
3.1	Pulse Receiver & Application	UST-PNS-4C	1	SET	₩55,000,000	₩55,000,000	
3.2	Probe	10K7I 45 PF50	4	PCS	₩2,500,000	₩10,000,000	Spare Parts포함
3.3	Programming Fee		40	M/D	₩300,000	₩12,000,000	
3.4	Chiller	Airmajor	1	PC	₩4,500,000	₩4,500,000	Heating포함
3.5	Floating Unit		1	SET	₩2,000,000	₩2,000,000	
3.6	UT Probe Unit	Misumi	2	SET	₩8,000,000	₩16,000,000	5축(회전Jig포함)
3.7	PC & Application Program	DELL	1	SET	₩20,000,000	₩20,000,000	UPS & AVR 포함
4	Marking						
4.1	Dot Marking	JEIL MTECK	1	SET	₩0	₩0	고객 사급
4.2	Marking Unit		1	SET	₩4,360,000	₩4,360,000	2기종 대응
5	AIR BLOW						
5.1	Air Blow Unit		1	SET	₩6,000,000	₩6,000,000	
5.2	Surge Tank		1	SET	₩6,000,000	₩6,000,000	
6	NG SHOOTER						
6.1	NG Shooter Unit		1	SET	₩4,000,000	₩4,000,000	
7	OUT STOCKER						
7.1	OUT STOCKER		1	SET	₩12,000,000	₩12,000,000	1열15PCS
8	ELECTRIC CONTROL SYSTEM						
8.1	PLC Electric Parts		1	SET	₩40,000,000	₩40,000,000	
8.2	Control & Operating Panel		1	SET	₩4,000,000	₩4,000,000	
8.3	Programming Fee		50	M/D	₩300,000	₩15,000,000	
8.4	Wiring Fee		40	M/D	₩250,000	₩10,000,000	
9	DESIGN & ASS'Y						
9.1	Design Fee		50	M/D	₩250,000	₩12,500,000	
9.2	Asembly		40	M/D	₩200,000	₩8,000,000	
9.3	Trial & Try-Out		40	M/D	₩200,000	₩8,000,000	
9.4	Transportation		1	SET	₩0	₩0	
SUB TOTAL						₩315,360,000	
10	Spare Parts						
10.1	Spare Parts					₩5,000,000	
11	ADMINISTRATIVE COST						
11.1	Management Expense/Profits			%			
TOTAL						₩320,360,000	

Remark

- Subject Work
 - FORD CX 483_23025-C4902 / C4912(CT:40sec)
- Process: Loading → UT Inspection → Air Blow → NG or OUT STOCKER.
- 검사 방법
 - 사각탐상(UST).
 - 추후 TEST 확인 필요.
- 제외 사항
 - 이종감지 제외
 - 상부 보전 사다리 제외
- 특이사항
 - UL 인증 포함
 - 현지 통역,교육자료 스페인어 대응 포함

2. 멕시코 현지 설치

(단위: 원)

NO	구 분	형식&규격	수량	단위	단가	금액	비고
1	SUPERVISOR FEE(1차)						
1.1	Electric Parts		6	MD	W250,000	W1,500,000	
1.2	PLC Software		6	MD	W250,000	W1,500,000	
1.3	Set up / Training		30	MD	W250,000	W7,500,000	
1.4	Mexico Translation		10	MD	W100,000	W1,000,000	
2	OP Training(2차,3차)						
2.1	Training/Mass production Support		36	MD	W250,000	W9,000,000	
2.2	Mexico Translation		10	MD	W100,000	W1,000,000	
2.3	Educational resource(Spanish)		1	SET	W11,000,000	W11,000,000	
2.4	UL Accreditation		1	SET	W12,000,000	W12,000,000	
3	MEXICO STAYOVER/FLIGHT						
3.1	Mexico stayover		44	MD	W150,000	W6,600,000	
3.2	Flight		9	SET	W2,171,700	W19,545,300	
4	ELECTRIC CONTROL SYSTEM						
4.1	PLC Electric Parts			SET	W0	W0	
4.2	Control & Operating Panel			SET	W0	W0	
4.3	Programming Fee			M/D	W0	W0	
4.4	Wiring Fee			M/D	W0	W0	
5	DESIGN & ASS'Y						
5.1	Design Fee			M/D	W0	W0	
5.2	Assembly			M/D	W0	W0	
5.3	Trial & Try-Out			M/D	W0	W0	
5.4	Transportation			SET	W0	W0	
SUB TOTAL						W70,645,300	
6	Spare Parts						
6.1	Spare Parts			%		W0	
7	ADMINISTRATIVE COST						
7.1	Management Expense/Profits		0	%		W0	
TOTAL						W70,645,300	

Remark