

見 積 書

見積番號： INT201115-01B

日 字： 2020 年 12月 15日

受 信： 현대위아 (주) 貴中

參 照： 貴下

營業擔當： 배상기 부장 (010-7548-2729)

下記 金額 및 條件으로 見積합니다.



대표 김 재 선



경남 양산시 산막공단북13길 49

TEL : 055 - 372 - 0167

FAX : 055 - 372 - 0168

見積金額： 一金 이억육천팔백만 원 整 (₩268,000,000)整 V.A.T 別途

멕시코 몬테레이_CVJ 3단계 증설 공사

項目 NO.	品 名 DESCRIPTION	規 格 SPECIFICATION	單位 UNIT	數量 Q'TY	單 價 UNIT PRICE	金 額 AMOUNT	備 考 REMARK
1	일 체형 IDS용 WASHING MACHINE		台	1	268,000,000	268,000,000	세부견적서 참조
2							
3							
4							
5							
6							
7							
8							
9							
10							
11							
12							
합계금액 (TOTAL AMOUNT)						₩ 268,000,000 (만단위 절삭)	

특기사항

- 1) 견적유효기간: 제출일로 부터 30일
- 2) 납 기: 계약일로 부터 100일
- 3) 지 불 조 건: 계약금 30%, 중도금 50%, 잔금 20%
- 4) 인 도 장 소: 부산항 F.O.B.
- 5) 설비 해포/안착 및 메인 UTYL ' 연결은 업무 제외
- 6)

項目 NO.	品 名 DESCRIPTION	規 格 SPECIFICATION	單位 UNIT	數量 Q'TY	單 價 UNIT PRICE	金 額 AMOUNT	備 考 REMARK
	일체형 IDS용 WASHING MACHINE		台	1		₩268,000,000	
	A. MACHINE PART						
	1. BASE EQUIPMENT						
	1) FRAME & MAIN BODY	SUS304/SS400	SET	1		9,000,000	
	2) TANK & PUMP BASE	SUS304/SS400	SET	1		6,000,000	
	3) AUTO SHUTTER	SUS304	SET	4	1,500,000	5,000,000	
	4) INSPECTION DOOR	SUS304	SET	6	400,000	2,400,000	
	5) COVER / FENCE & ACC'RY	SS400	SET	1		3,000,000	
	6) ROOM 내부 방음장치 (AIR BLOW)	SUS304+흡음재	SET	1		800,000	
	2. TRANSFER SYSTEM						
	1) MAIN CONVEYOR SYSTEM		SET	1		5,000,000	
	* ATTACHMENT SUS CHAIN	RS2060					TSUBAKI
	* CHAIN GUIDE & BRACKET	SUS304					
	* MOTOR + INVERTER						SIEMENS
	2) WORK 안착 PALLET UNIT	SUS304	SET	40	400,000	16,000,000	
	3) JIG CLAMP UNIT	SS400	SET	2	1,800,000	3,600,000	
1	3. WASHING SYSTEM	<u>2 ST.</u>					
	1) NOZZLE & SOCKET	SUS304	PCS	60	10,000	600,000	
	2) N/Z CHAMBER	SS400	SET	1		2,500,000	
	3) NOZZLE UP-DOWN	SS400	SET	1		2,000,000	
	4) WASHING CURCUIT UNIT		SET	1		3,000,000	
	5) FITT'G & PIPING	SUS304	SET	1		1,700,000	
	4. AIR BLOW SYSTEM	<u>3 ST.</u>					
	1) NOZZLE & SOCKET	SUS304	PCS	60	10,000	600,000	
	2) N/Z CHAMBER	SS400	SET	1		2,500,000	
	3) NOZZLE UP-DOWN UNIT	SS400	SET	1		2,000,000	
	4) AIR BLOW CURCUIT UNIT		SET	1		1,800,000	
	5) FITT'G & PIPING	SGP	SET	1		1,000,000	
	5. HOT BLOW SYSTEM	<u>4 ST.</u>					
	1) BLOW UNIT (UL 불가)	WK-14KK	SET	1		1,900,000	WONKWANG
	2) BLOW CHAMBER	SS400	SET	1		1,000,000	
	3) FITT'G & PIPING	SS400	SET	1		250,000	

項目 NO.	品 名 DESCRIPTION	規 格 SPECIFICATION	單位 UNIT	數量 Q'TY	單 價 UNIT PRICE	金 額 AMOUNT	備 考 REMARK
1	6. SPECIAL EQUIPMENT						
	1) WASHING PUMP	8K*400 l	SET	1		3,500,000	GRUNDFOS
	2) WASHING VALVE	10K	SET	1		2,000,000	CKD
	3) FILTER PUMP	2K*400 l	SET	1		2,200,000	GRUNDFOS
	4) MESH BASKET FILTER UNIT	400 l x 80MESH	SET	2	1,000,000	2,000,000	
	5) BAG FILTER	50μm*500 l /min	SET	2	2,000,000	4,000,000	
	6) FILTERING CURCUIT UNIT		SET	1		2,500,000	
	7) FILTERING PIPING & ACC'RY	SUS304	SET	1		1,500,000	
	8) FLOATING SWITCH		SET	2	400,000	800,000	
	9) AERATION SYSTEM		SET	1		500,000	
	10) ELECTRIC HEATER (UL 불가)	10Kw	SET	4	180,000	720,000	WONKWANG
	11) OIL SKIMMER (BELT)	5.5 l /h	SET	1		900,000	ABANAKI
	12) AIR SURGE TANK	1.0m³	SET	1		1,100,000	인증품
	13) LUBRICATION SYSTEM	AUTO	SET	1		500,000	KFG
	7. PNEUMATIC SYSTEM						
	1) FRT & VALVE STAND UNIT		SET	1		2,500,000	FESTO
	2) FITT'G & PIP'G		SET	1		500,000	
	8. ELECTRIC CONTROL SYSTEM						
	1) MAIN CONTROL PANEL		SET	1		25,000,000	SIEMENS
	2) MAIN OPERATION PANEL		SET	1		3,500,000	SIEMENS
	3) LOCAL 자재 (SENSOR,CABLE,DUCT,R/T 등)		SET	1		7,500,000	
	4) LOCAL 공사 및 시운전		SET	1		17,000,000	
	5) 설계,PROGRAM 및 작화		SET	1		4,000,000	
	SUB TOTAL-1					153,870,000	
	B. ENGINEERING FEE		M/D	30	200,000	6,000,000	
	C. ASSEMBLY FEE		M/D	30	200,000	6,000,000	
	D. 포장 & 운송비 & 중장비 대여						
	1) 설비 포장비	WOOD PACKING	CBM	48	85,000	4,080,000	
	2) 운송비	부산항 F.O.B	式	1		300,000	
	E. 설치 & 시운전						MEXICO
	1) 현지 해포 및 설치 중장비 대여		式	1			- 업무제외
	2) 현지 설치비	기계 & 전기	M/D	40	450,000	18,000,000	숙식 및 경비포함
	3) 현지 시운전비	기계 & 전기	M/D	30	450,000	13,500,000	숙식 및 경비포함

