

Q U O T A T I O N

10-Jun-21

현대위아(주)

귀중

아래와 같이 견적을 제출 합니다.

일금(V.A.T 별도) ₩498,500,000

tic

티 아 이 씨 (주)

대표이사 : 정 봉 채

주 소 : 경남 창원시 팔용동 21-1

INNER RECE 외경연삭

Page 1/2

NO.	품 명	규격	수량	단가	금액	비고
1	INNER RECE 외경연삭					
	SGE-400 (h)		1 대	194,300,000	194,300,000	
	연삭기 OPTION 비용		1 식	98,700,000	98,700,000	
	자동화 장치 일체		1 식	125,000,000	125,000,000	
	설치 및 시운전 비용		1 식	80,500,000	80,500,000	

* 전원 220V , 3상 60Hz

* 유첨 : 상세내역 참조

HYUNDAI WIA

대외비(Restricted) / 설비구매팀 / 이태호

합 계	498,500,000
-----	-------------

견적 유효 기간 30일

납 기 발주 후 8개월

대금 결제 방법 계약금 30%

중도금 60% (입회검사 및 장비입고시)

잔금 10% (시운전 완료 후)

견적 담당자 영업팀 부장 김동수(010-8877-6589)

TEL / FAX 055-255-5051 / 055-297-1923

E-mail dsk505@hanmail.net



D. S. KIM, General Manager

■ 견적 상세 내역

NO	DESCRIPTION	MODEL	UNIT	Q'TY	UNIT PRICE	AMOUNT	REMARKS
1	내륜 외경 연삭기	SGE-400 (h)	대	1	185,000,000	185,000,000	
	□ 표준 사양 내용						
	- 2 축 SERVO MOTOR & DRIVE SYSTEM(MITSUBISHI)						
	- G/W SLIDE & DRESS SLIDE UNIT (2 축) : 표준사양						
	- HYD CHUCK TYPE WORK HEAD (400~1,200RPM)						
	(W/H 전후 이동거리 50MM)						
	가공외경범위 : 25 ~ 70mm						
	가공 폭 범위 : 10 ~40mm						
	- WORK HEAD SWIVEL BASE (주축 선회각도 0~5°)						
	- SPECIAL HYDRAULIC(COLLET) CHUCK SYSTEM						
	- 1AXIS DRESS SLIDE UNIT						
	- HYDRO-STATIC TYPE G/W SPINDLE UNIT						
	- G/W 외경: PHI 510 회전수 : 2,500RPM						
	- G/W MOTOR 7.5 KW						
	- HYDRAULIC TANK UNIT(40LITER*2)						
	- CENTRAL LUBRICATION SYSTEM						
	- BOX TYPE MACHINE COVER						
	- 설비내부 IN(OUT) CHUTE 포함						
	- MAIN 전원 220V 3PHASE (415V 50Hz)						
	- SOL' CONTROL 전압 DC 24V						
	부속장치 및 기타					9,300,000	
	- STANDARD HAND TOOL		SET	1	800,000		
	- WORKING TOOL & JIG		SET	1	8,500,000		
	.SHOE ASSY'외 TOOL류 (1SET)						
	.IN/OUT TOOL						
	.G/W , DRESSER DIA'				사급 기준		
2	OPTION						
	- IN/OUT CHUTE & PUSHER TYPE (UN)LOADING UNIT		SET	1	16,500,000	16,500,000	
	- ROTARY FORM DRESSER SPINDLE(85PHI/4,000RPM)		SET	1	5,600,000	5,600,000	
	- GAP CONTROL SYSTEM (ACCRETECH)		SET	1	6,000,000	6,000,000	
	- GAUGE CYLINDER UNIT		SET	1	5,600,000	5,600,000	
	- IN-PROCESS GAUGE UNIT(ACCRETECH)		SET	1	15,700,000	15,700,000	
	- MIST COLLECTOR(REVEN)		SET	1	7,300,000	7,300,000	
	- COOLANT TANK UNIT(800LITER):CHILLER포함		SET	1		40,000,000	
	MAGNET SEPERATOR & CHAIN SCRAPER FILTERING SYSTEM (수용성연삭유 기준)						
	- 지정색상		SET	1	2,000,000	2,000,000	
3	자동화 장치 일체		SET	1		125,000,000	
4	설치 시운전 (10일 기준)						
	- 본기 BOX 포장 및 운반(FOB BUSAN)		식	1	4,500,000	4,500,000	
	- 부대장치 BOX 포장 및 운반(FOB BUSAN)		식	1	7,000,000	7,000,000	
	- 인도 출장 항공료 외 이동비용		인	10	2,400,000	24,000,000	
	- 출장 공사 인건비		MD	100	300,000	30,000,000	
	- HOTEL 숙박비 외		MD	100	150,000	15,000,000	
	TOTAL					498,500,000	

* 상기 사양 및 견적은 세부 사양 협의시 변경될 수 있습니다.