

見 積 書

2021 年 09 月 30 日

현대 위아 주식회사 貴下

下記와 如히 見積하나다.



(주) 와스텍 지점
WASTECH INSTITUTE CO., LTD.

工 事 名 : 외륜 피막LINE 인도 설치(건)

工 事 金 額 : 질억삼천오백만원정 ₩735,000,000

契 約 條 件 : 계약금 30%, 중도금 50%, 잔금 20%

納 期 : 발주일로 부터 180 일

有 效 期 間 : 견적일로 부터 30 일

문 서 번 호 : WST21-09-001

(V.A.T 별도)

	品 名	規 格	數 量	單 位	單 價	金 額
1-0	WASHING EQUIPMENT #1		1	LOT		100,408,000
2-0	피막 EQUIPMENT #2		1	LOT		155,277,000
3-0	WASHING EQUIPMENT #3		1	LOT		113,926,000
4-0	AUTO LOADER SYSTEM		2	LOT		40,000,000
5-0	ROBOT SYSTEM		1	LOT		43,500,000
6-0	ELECTRICAL SYSTEM		1	LOT		58,377,400
7-0	기존 도장라인 전기장치 제작 및 설치비		1	LOT		25,000,000
8-0	기존 도장라인 ROBOT 프로그램 및 안전휰스 제작 설치		1	LOT		10,000,000
9-0	실리콘 마스크킹4종 제작비(금형 4종)		1	LOT		8,500,000
10-0	OVER HAND COST		1	LOT		78,500,000
	도장비		1	LOT		5,000,000
	국내 현장설치 공사 및 시운전		1	LOT		3,500,000
	기업이윤 및 공과잡비		1	LOT		70,000,000
						₩ 633,488,400
11-0	PACKING		1	LOT		19,047,600
12-0	FOB BUSAN		1	LOT		11,889,000
13-0	INSTALLATION (1차-기계,전기 현장설치 시운전)		1	LOT		70,575,000
						₩ 101,511,600
TOTAL AMOUNT					₩ 735,000,000	

OUT OF SCOPE

- 1차 UTILITY (전기, 물, 에어) , 기존장비(건조로,방청,OUT STOCKER) 이설 및 개조비
- 인허가 件 (대기, 수질) , 3. 환경설비 & 배기DUCT(옥외) 4. 피막 약품 및 건축 & 전도도측정시스템 5. 보전 SPARE

PARTS

	品 名	規 格	數 量	單 位	單 價	金 額
1-0	WASH EQUIPMENT #1					₩ 100,408,000
1	BASE OF EQUIPMENT					₩ 3,008,500
	! SIZE : 1,700W × 5,000L × 100H (LOAD AND UNAD FRAME 포함)					
	! MAT'L : SS 41					
	1) 원 부자재비					
	! ANGLE	50 × 6T	80	KG	1,700	136,000
	! CHANNEL	100 × 50 × 6T	350	KG	1,700	595,000
	! STEEL PLATE	6T ~ 10T	150	KG	1,650	247,500
	! 표면처리비 (SANDIG AND PAINTING)		600	KG	550	330,000
	! 부자재비 (WEEDING BAR 외)		1	LOT		200,000
	2) MANUFACTURING FEE		10	M/D	150,000	1,500,000
2	PROCESS TANK (탈지)					₩ 9,055,750
	! SIZE : 1000W×1,500L×700H					
	! MAT'L : 304 STAINLESS STEEL					
	ALL HEATDE WASH TANK UILL BE INSULATED (ISO-PINK)					
	HOT WATER TANK					
	1) 원 부자재비					
	! PLATE	4T	850	KG	4,500	3,825,000
	! PLATE	2T	85	KG	4,650	395,250
	! CHANNEL	75 × 40 × 6T(SS41)	145	KG	1,700	246,500
	! ANGLE	50 × 6T	90	KG	5,200	468,000
	! FLANGE	65 × 10KG/cm ²	3	EA	35,000	105,000
	! FLANGE	40 × 10KG/cm ²	2	EA	28,000	56,000
	! PIPE	65A × 40 SCH	1	M		85,000
	! PIPE	50A × 40 SCH	1	M		70,000
	! PIPE	40A × 40 SCH	1	M		60,000
	! 보온재 (ISO-PINK)	1 × 2 × 50T	7	SH	25,000	175,000
	! FILTER 망	400W × 500L	4	EA	75,000	300,000
	! DOOR	600W × 500L	1	EA	120,000	120,000
	! 기타 부자재비		1	LOT		350,000
	2) MANUFACTURING FEE					
	! 절단비					250,000
	! 밴딩비					300,000
	! 용접, 사상, 조립		15	M/D	150,000	2,250,000

	品名	規格	數量	單位	單價	金額
3	PROCESS TANK (수세)		1	坩	8,476,750	<u>₩ 8,476,750</u>
	! SIZE : 800W×1,500L×700H					
	! MAT'L : 304 STAINLESS STEEL					
	ALL HEATDE WASH TANK UILL BE INSULATED (ISO-PINK)					
	HOT WATER TANK					
	1) 원 부자재비					
	! PLATE	4T	750	KG	4,500	3,375,000
	! PLATE	2T	85	KG	4,650	395,250
	! CHANNEL	75 × 40 × 6T(SS41)	135	KG	1,700	229,500
	! ANGLE	50 × 6T	80	KG	5,200	416,000
	! FLANGE	65 × 10KG/cm ²	2	EA	35,000	70,000
	! FLANGE	40 × 10KG/cm ²	2	EA	28,000	56,000
	! PIPE	65A × 40 SCH	1	M		85,000
	! PIPE	50A × 40 SCH	1	M		70,000
	! PIPE	40A × 40 SCH	1	M		60,000
	! 보온재 (ISO-PINK)	1 × 2 × 50T	6	SH	25,000	150,000
	! FILTER 망	400W × 500L	4	EA	75,000	300,000
	! DOOR	600W × 500L	1	EA	120,000	120,000
	! 기타 부자재비		1	LOT		350,000
	2) MANUFACTURING FEE					
! 절단비					250,000	
! 밴딩비					300,000	
! 용접, 사상, 조립		15	M/D	150,000	2,250,000	
4	MAIN BODY (SPRAY-ROOM)					<u>₩ 15,849,500</u>
	! SIZE : 1000W × 3,700L × 1350H					
	! MAT'L : 304 STAINLESS STEEL					
	! 제작시방					
	☞ WASH STRUCTURE : SUS 304 ANGLE 50 × 50 × 5mm THICK					
	(PLATE 3T) SUS 304 STEEL					
	☞ ALL HEATED SPRAY ENCLOSURES ARE 은 INSULATION					
	☞ DOOR은 각 공정 SPRAY ROOM 마다설치 (SPRAY ROOM 내부 볼수 있도록 제작)					
	1) 원 부자재비					
	! ANGLE	50 × 5T	350	KG	3,870	1,354,500

	品 名	規 格	數 量	單 位	單 價	金 額
5	! PLATE	2T	100	KG	4,650	465,000
	! PLATE	3T	1200	KG	4,500	5,400,000
	! 보온재 (ISO-PINK)	1 × 2 × 50T	20	SH	25,000	500,000
	! DOOR (점검구외)	500W × 600L	8	SET	185,000	1,480,000
	! 부자재비 (PAKING 류외 5종)		1	LOT		500,000
	2) MANUFACTURING FEE					
	! 절단비		1	LOT		850,000
	! 밴딩비		1	LOT		800,000
	! 용접, 사상, 조립		30	M/D	150,000	4,500,000
	CONVEYOR DRIVE EQ'					<u>₩ 16,767,500</u>
	∴ 제작시방					
	! CONVEYOR SPEED : 0~2M/MIN					
	! DRIVE EL. MOTER : 1750 RPM/min × 0.75KW					
	! GEAR REDUER MESH BELT					
	MAT'L : 304 STAINLESS STEEL					
6	1) 원 부자재비					
	! DRIVE EL. MOTOR	0.75KW	1	SET		150,000
	! GEAR REDUCER	1/385	1	SET		450,000
	! CONVEYOR & 제품JIG	13M÷P150=87 × 2EA	174	EA	75,000	13,050,000
	! SPROCKET	23NT	4	EA	220,000	880,000
	! SHAFT	φ50 × 1350L	2	EA	238,000	476,000
	! 부자재비 (BEARING 외 4종)		1	LOT		511,500
	! TENSION EQ'		2		250,000	500,000
	2) MANUFACURING FEE		5	M/D	150,000	750,000
	SPRAY SYSTEM (탈지)					<u>₩ 11,300,000</u>
	∴ 제작시방					
	! SPRAY SYSTEM					
	TYPE : VERTICAL					
	ELECTRIC MOTOR : 2P × 2HP					
	MAT'L : 316 STAINLESS					
	! SPRAY NOZZLE					

	品名	規格	數量	單位	單價	金額
	SPRAY : 3.8MM DIANMETER SPRAY Q'TY : 9.5LIT/MIN SPRAY ANGLE : 60 DEGREE NOZZLE TYPE : VEE JET (FULL CONE/FLAT) MAT'L : 304 STAINLESS ! PIPING SYSTEM SIZE : 25A ~ 40A MAT'L : 304 STAINLESS PUMP OUT LET에 온도계 및 압력계 부착 1) 원 부자재비 ! PUMP ! NOZZLE ! 자유 조인트 ! 부 자재비 ! PIPING (VALVE 외 12종) 2) MANUFACTURING FEE					
		350ℓ/min	2	SET	2,850,000	5,700,000
		FULL CONE	70	EA	12,500	875,000
		3/8 SS	70	EA	17,500	1,225,000
			1	LOT		500,000
			1	LOT		1,500,000
			10	M/D	150,000	1,500,000
7	SPRAY SYSTEM (수세) ∴ 제작시방 ! SPRAY SYSTEM TYPE : VERTICAL ELECTRIC MOTOR : 2P × 2HP MAT'L : 316 STAINLESS ! SPRAY NOZZLE SPRAY : 3.8MM DIANMETER SPRAY Q'TY : 9.5LIT/MIN SPRAY ANGLE : 60 DEGREE NOZZLE TYPE : VEE JET (FULL CONE/FLAT) MAT'L : 304 STAINLESS ! PIPING SYSTEM SIZE : 25A ~ 40A MAT'L : 304 STAINLESS PUMP OUT LET에 온도계 및 압력계 부착 1) 원 부자재비 ! PUMP		1	垠	9,800,000	<u>₩ 9,800,000</u>
		350ℓ/min	1	SET		2,850,000

	品 名	規 格	數 量	單 位	單 價	金 額
	! NOZZLE	FULL CONE	50	EA	12,500	625,000
	! 자유 조인트	3/8 SS	50	EA	17,500	875,000
	! 부 자재비		1	LOT		500,000
	! PIPING (VALVE 외 12종)		1	LOT		1,200,000
	2) MANUFACTURING FEE		8	M/D	150,000	1,200,000
	PRESSURE : 20 PSI					
	PIPING : MAT'L : 304 STAINLESS STEEL					
	SIZE : 20A ~ 40A					
	CONTROL VALVE : 25A BALL					
	1) 원 부자재비					
	! AIR CONTROL UNIT 외		1	LOT		500,000
	! AIR NOZZLE		3	SET	100,000	300,000
	! PIPING		1	LOT		250,000
	2) MANUFACTURING FEE		10	M/D	150,000	1,500,000
8	BLOW OFF SYSTEM					₩ 3,100,000
	∴ 제작시방					
	! AIR BLOW (공장 AIR 사용)					
	AIR NOZZLE : TYPE : WIND JET					
	PRESSURE : 20 PSI					
	PIPING : MAT'L : 304 STAINLESS STEEL					
	SIZE : 20A ~ 40A					
	CONTROL VALVE : 25A BALL					
	1) 원 부자재비					
	! AIR CONTROL UNIT 외	BY-PASS	1	LOT		500,000
	! AIR NOZZLE		5	SET	120,000	600,000
	! PIPING		2	LOT	250,000	500,000
	2) MANUFACTURING FEE		10	M/D	150,000	1,500,000
9	EXHAUST SYSTEM					₩ 5,350,000
	∴ 제작시방					
	! 장비의 입구와 출구쪽에 VENTILATION 장치를 설치함					
	VENT. TAN : VOLUME : 30m ³ /min × 120mmAq					

	品 名	規 格	數 量	單 位	單 價	金 額
	MAT'L 304 STAINLESS STEEL ! HOOD AND DUCT MAT'L : 304 STAINLESS STEEL 1) 원 부자재비 ! EXHAUST FAN ! HOOD AND DUCT 2) MANUFACTURING FEE		1 10	LOT M/D	150,000	3,850,000 1,500,000
10	OIL SEPARATION AND CHIP FILTER EQ' (탈지 ZONE) ∴ 제작시방 ! 적용범위 : STAGE 1 TANK (ALKALINE CL.) 작업공정에서 발생하는 OIL MIST를 제거하기 위한 장치 1) CHIP FILTER 2) OIL SKIMMER ! PIPING 3) MANUFACTURING FEE	20 - 40A	1 1 1 5	SET SET LOT M/D	150,000	<u>₩ 3,950,000</u> 1,550,000 1,200,000 450,000 750,000
11	HEATING SYSTEM (열원 : 전기) 탈지, 수세#1 ∴ 제작시방 ! THE HEATER CAPACITY IS AS FOLLOWS DEBONDELUBE 60 DEG.C - 1) HEATER TYPE : TUBE MAT'L : SUS 304 2) MANUFACTURING FEE	10KW	10 5	EA M/D	280,000 150,000	<u>₩ 3,550,000</u> 2,800,000 750,000
12	PIPING SYSTEM ∴ 제작시방 1) 원 부자재비 ! WATER SUPPLY MAT'L : SUS 304 SIZE : 20A ~ 40A ! DRAIN LINE MAT'L : SUS 304 SIZE : 40A		1 1	LOT LOT		<u>₩ 10,200,000</u> 500,000 450,000

	品 名	規 格	數 量	單 位	單 價	金 額
2-0	TANK DRAIN V/V은 BALL V/V 부착					
	! Air By pass & Pipping		1	LOT		8,500,000
	2) MANUFACTURING FEE		5	M/D	150,000	750,000
	피막 EQUIPMENT #2					₩ 155,277,000
	1	BASE OF EQUIPMENT				<u>₩ 3,008,500</u>
	! SIZE : 1,700W × 5,000L × 100H (LOAD AND UNAD FRAME 포함)					
	! MAT'L : SS 41					
	1) 원 부자재비					
	! ANGLE	50 × 6T	80	KG	1,700	136,000
	! CHANNEL	100 × 50 × 6T	350	KG	1,700	595,000
	! STEEL PLATE	6T ~ 10T	150	KG	1,650	247,500
	! 표면처리비 (SANDIG AND PAINTING)		600	KG	550	330,000
	! 부자재비 (WEEDING BAR 외)		1	LOT		200,000
	2) MANUFACTURING FEE		10	M/D	150,000	1,500,000
	2	PROCESS TANK (표면조정)				<u>₩ 8,526,750</u>
	! SIZE : 800W×1,500L×700H					
	! MAT'L : 316 STAINLESS STEEL					
	ALL HEATDE WASH TANK UILL BE INSULATED (ISO-PINK)					
	HOT WATER TANK					
	1) 원 부자재비					
	! PLATE	4T	750	KG	4,500	3,375,000
	! PLATE	2T	85	KG	4,650	395,250
	! CHANNEL	75 × 40 × 6T(SS41)	135	KG	1,700	229,500
	! ANGLE	50 × 6T	80	KG	5,200	416,000
	! FLANGE	65 × 10KG/cm ²	2	EA	35,000	70,000
	! FLANGE	40 × 10KG/cm ²	2	EA	28,000	56,000
	! PIPE	65A × 40 SCH	1	M		85,000
	! PIPE	50A × 40 SCH	1	M		100,000
	! PIPE	40A × 40 SCH	1	M		80,000
	! 보온재 (ISO-PINK)	1 × 2 × 50T	6	SH	25,000	150,000
	! FILTER 망	400W × 500L	4	EA	75,000	300,000
	! DOOR	600W × 500L	1	EA	120,000	120,000
	! 기타 부자재비		1	LOT		350,000

	品 名	規 格	數 量	單 位	單 價	金 額
3	2) MANUFACTURING FEE					
	! 절단비					250,000
	! 밴딩비					300,000
	! 용접, 사상, 조립		15	M/D	150,000	2,250,000
	PROCESS TANK (피막)					<u>₩ 13,920,750</u>
	! SIZE : 2000W×1,500L×700H					
	! MAT'L : 316L STAINLESS STEEL					
	ALL HEATDE WASH TANK UILL BE INSULATED (ISO-PINK)					
	HOT WATER TANK					
	1) 원 부자재비					
	! PLATE	4T	1500	KG	4,500	6,750,000
	! PLATE	2T	85	KG	4,650	395,250
	! CHANNEL	75 × 40 × 6T(SS41)	145	KG	1,700	246,500
	! ANGLE	50 × 6T	90	KG	5,200	468,000
	! FLANGE	65 × 10KG/cm ²	3	EA	35,000	105,000
	! FLANGE	40 × 10KG/cm ²	2	EA	28,000	56,000
	! PIPE	65A × 40 SCH	2	M		150,000
	! PIPE	50A × 40 SCH	1	M		100,000
	! PIPE	40A × 40 SCH	1	M		80,000
	! 보온재 (ISO-PINK)	1 × 2 × 50T	20	SH	25,000	500,000
4	! FILTER 망	400W × 500L	4	EA	75,000	300,000
	! DOOR	600W × 500L	1	EA	120,000	120,000
	! 기타 부자재비		1	LOT		350,000
	2) MANUFACTURING FEE					
	! 절단비					250,000
	! 밴딩비					300,000
	! 용접, 사상, 조립		25	M/D	150,000	3,750,000
	MAIN BODY (SPRAY-ROOM)					<u>₩ 16,015,000</u>
	! SIZE : 1000W × 3,800L × 1350H					
	! MAT'L : 316L STAINLESS STEEL					
	! 제작시방					

	品名	規格	數量	單位	單價	金額
5	☞ WASH STRUCTURE : SUS 316 ANGLE 50 × 50 × 5mm THICK (PLATE 3T) SUS 316L STEEL					
	☞ ALL HEATED SPRAY ENCLOSURES ARE 은 INSULATION					
	☞ DOOR은 각 공정 SPRAY ROOM 마다설치 (SPRAY ROOM 내부 볼수 있도록 제작)					
	1) 원 부자재비					
	! ANGLE	50 × 5T	350	KG	5,200	1,820,000
	! PLATE	2T	100	KG	4,650	465,000
	! PLATE	3T	1300	KG	4,500	5,850,000
	! 보온재 (ISO-PINK)	1 × 2 × 50T	20	SH	25,000	500,000
	! DOOR (점검구외)	500W × 600L	8	SET	185,000	1,480,000
	! 부자재비 (PAKING 류외 5종)		1	LOT		500,000
	2) MANUFACTURING FEE					
	! 절단비		1	LOT		850,000
	! 밴딩비		1	LOT		800,000
	! 용접, 사상, 조립		25	M/D	150,000	3,750,000
	CONVEYOR DRIVE EQ'					<u>₩ 18,206,000</u>
	∴ 제작시방					
	! CONVEYOR SPEED : 0~2M/MIN					
	! DRIVE EL. MOTER : 1750 RPM/min × 0.75KW					
	! GEAR REDUER MESH BELT					
	MAT'L : 304 STAINLESS STEEL					
	1) 원 부자재비					
	! DRIVE EL. MOTOR	0.75KW	1	SET		150,000
	! GEAR REDUCER	1/385	1	SET		450,000
	! CONVEYOR(FLAT MESH)	13M÷P150=87 × 2EA	174	EA	75,000	13,050,000
	! SPROCKET	23NT	4	EA	220,000	880,000
	! SHAFT	φ50 × 1350L	2	EA	238,000	476,000
	! 부자재비 (BEARING 외 4종)		1	LOT		500,000
	! TENSION EQ'		2		225,000	450,000
	2) MANUFACURING FEE		15	M/D	150,000	2,250,000
6	SPRAY SYSTEM (표면조정)		1	台	10,100,000	<u>₩ 10,100,000</u>
	∴ 제작시방					
	! SPRAY SYSTEM					

	品 名	規 格	數 量	單 位	單 價	金 額
	TYPE : VERTICAL ELECTRIC MOTOR : 2P × 2HP MAT'L : 316 STAINLESS ! SPRAY NOZZLE SPRAY : 3.8MM DIANMETER SPRAY Q'TY : 9.5LIT/MIN SPRAY ANGLE : 60 DEGREE NOZZLE TYPE : VEE JET (FULL CONE/FLAT) MAT'L : 304 STAINLESS ! PIPING SYSTEM SIZE : 25A ~ 40A MAT'L : 304 STAINLESS PUMP OUT LET에 온도계 및 압력계 부착 1) 원 부자재비 ! PUMP ! NOZZLE ! 자유 조인트 ! 부 자재비 ! PIPING (VALVE 외 12종) 2) MANUFACTURING FEE					
		350ℓ/min	1	SET		2,850,000
		FULL CONE	50	EA	12,500	625,000
		3/8 SS	50	EA	17,500	875,000
			1	LOT		500,000
			1	LOT		1,200,000
			10	M/D	150,000	1,500,000
	PRESSURE : 20 PSI PIPING : MAT'L : 304 STAINLESS STEEL SIZE : 20A ~ 40A CONTROL VALVE : 25A BALL 1) 원 부자재비 ! AIR CONTROL UNIT 외 ! AIR NOZZLE ! PIPING 2) MANUFACTURING FEE					
			1	LOT		500,000
			3	SET	100,000	300,000
			1	LOT		250,000
			10	M/D	150,000	1,500,000
7	BLOW OFF SYSTEM ∴ 제작시방 ! AIR BLOW (공장 AIR 사용) AIR NOZZLE : TYPE : WIND JET PRESSURE : 20 PSI					
						₩ 3,100,000

	品 名	規 格	數 量	單 位	單 價	金 額
	PIPING : MAT'L : 304 STAINLESS STEEL SIZE : 20A ~ 40A CONTROL VALVE : 25A BALL					
	1) 원 부자재비					
	! AIR CONTROL UNIT 외	BY-PASS	1	LOT		500,000
	! AIR NOZZLE		5	SET	120,000	600,000
	! PIPING		2	LOT	250,000	500,000
	2) MANUFACTURING FEE		10	M/D	150,000	1,500,000
8	SPRAY SYSTEM (피막)					<u>₩ 18,950,000</u>
	∴ 제작시방					
	! SPRAY SYSTEM					
	TYPE : VERTICAL					
	ELECTRIC MOTOR : 2P × 2HP					
	MAT'L : 316 STAINLESS					
	! SPRAY NOZZLE					
	SPRAY : 3.8MM DIANMETER					
	SPRAY Q'TY : 9.5LIT/MIN					
	SPRAY ANGLE : 60 DEGREE					
	NOZZLE TYPE : VEE JET (FULL CONE/FLAT)					
	MAT'L : 304 STAINLESS					
	! PIPING SYSTEM					
	SIZE : 25A ~ 40A					
	MAT'L : 316L STAINLESS					
	PUMP OUT LET에 온도계 및 압력계 부착					
	1) 원 부자재비					
	! PUMP(케미칼)	350ℓ/min	2	SET	3,850,000	7,700,000
	! NOZZLE	FULL CONE	150	EA	12,500	1,875,000
	! 자유 조인트	3/8 SS	150	EA	17,500	2,625,000
	! 부 자재비		1	LOT		500,000
	! PIPING (VALVE 외 12종)		1	LOT		2,500,000
	2) MANUFACTURING FEE		25	M/D	150,000	3,750,000
9	EXHAUST SYSTEM					<u>₩ 5,350,000</u>
	∴ 제작시방					

	品 名	規 格	數 量	單 位	單 價	金 額
	! 장비의 입구와 출구쪽에 VENTILATION 장치를 설치함 VENT. TAN : VOLUME : 30m ³ /min × 120mmAq Q'YT : 1 SET MAT'L 304 STAINLESS STEEL ! HOOD AND DUCT MAT'L : 304 STAINLESS STEEL 1) 원 부자재비 ! EXHAUST FAN ! HOOD AND DUCT 2) MANUFACTURING FEE		1 10	LOT M/D	150,000	3,850,000 1,500,000
10	HEATING SYSTEM (열원 : 전기) 표면조정, 피막 ∴ 제작시방 ! THE HEATER CAPACITY IS AS FOLLOWS DEBONDELUBE 60 DEG.C – 1) HEATER TYPE : TUBE MAT'L : SUS 316L 2) MANUFACTURING FEE	10KW	10 5	EA M/D	280,000 150,000	2,800,000 750,000
11	PIPING SYSTEM ∴ 제작시방 1) 원 부자재비 ! WATER SUPPLY MAT'L : SUS 316L SIZE : 20A ~ 40A ! DRAIN LINE MAT'L : SUS 316L SIZE : 50A TANK DRAIN V/V은 BALL V/V 부착 ! Air By pass & Pipping 2) MANUFACTURING FEE		1 10	LOT M/D		500,000 8,500,000 1,500,000
12	FILTERING SYSTEM & DUMP TANK FILTER EQ' (수동TYPE) AIR PUMP(PP, PVDF) & PIPING & DUMP TANK		1 1	LOT LOT		18,500,000 25,000,000

₩ 3,550,000

₩ 11,050,000

₩ 43,500,000

	品 名	規 格	數 量	單 位	單 價	金 額
3-0	WASH EQUIPMENT #3					₩ 113,926,000
1	BASE OF EQUIPMENT					₩ 3,911,500
	! SIZE : 1,700W × 7,000L × 100H (LOAD AND UNAD FRAME 포함)					
	! MAT'L : SS 41					
	1) 원 부자재비					
	! ANGLE	50 × 6T	100	KG	1,700	170,000
	! CHANNEL	100 × 50 × 6T	420	KG	1,700	714,000
	! STEEL PLATE	6T ~ 10T	150	KG	1,650	247,500
	! 표면처리비 (SANDIG AND PAINTING)		600	KG	550	330,000
	! 부자재비 (WEEDING BAR 외)		1	LOT		200,000
	2) MANUFACTURING FEE		15	M/D	150,000	2,250,000
2	PROCESS TANK (수세1탑 , 탕세1탑)		2	탑	8,511,750	₩ 17,023,500
	! SIZE : 800W×1,500L×700H					
	! MAT'L : 304 STAINLESS STEEL					
	ALL HEATDE WASH TANK UILL BE INSULATED (ISO-PINK)					
	HOT WATER TANK					
	1) 원 부자재비					
	! PLATE	4T	750	KG	4,500	3,375,000
	! PLATE	2T	85	KG	4,650	395,250
	! CHANNEL	75 × 40 × 6T(SS41)	125	KG	1,700	212,500
	! ANGLE	50 × 6T	90	KG	5,200	468,000
	! FLANGE	65 × 10KG/cm ²	2	EA	35,000	70,000
	! FLANGE	40 × 10KG/cm ²	2	EA	28,000	56,000
	! PIPE	65A × 40 SCH	1	M		85,000
	! PIPE	50A × 40 SCH	1	M		70,000
	! PIPE	40A × 40 SCH	1	M		60,000
	! 보온재 (ISO-PINK)	1 × 2 × 50T	6	SH	25,000	150,000
	! FILTER 망	400W × 500L	4	EA	75,000	300,000
	! DOOR	600W × 500L	1	EA	120,000	120,000
	! 기타 부자재비		1	LOT		350,000
	2) MANUFACTURING FEE					
	! 절단비 & 밴딩비					550,000
	! 용접, 사상, 조립		15	M/D	150,000	2,250,000

	品 名	規 格	數 量	單 位	單 價	金 額
3	MAIN BODY (SPRAY-ROOM)					<u>₩ 17,535,000</u>
	! SIZE : 1000W × 3,700L × 1350H					
	! MAT'L : 304 STAINLESS STEEL					
	! 제작시방					
	☞ WASH STRUCTURE : SUS 304 ANGLE 50 × 50 × 5mm THICK					
	(PLATE 3T) SUS 304 STEEL					
	☞ ALL HEATED SPRAY ENCLOSURES ARE 은 INSULATION					
	☞ DOOR은 각 공정 SPRAY ROOM 마다설치 (SPRAY ROOM 내부 볼수 있도록 제작)					
	1) 원 부자재비					
	! ANGLE	50 × 5T	350	KG	5,200	1,820,000
	! PLATE	2T	100	KG	4,650	465,000
	! PLATE	3T	1500	KG	4,500	6,750,000
	! 보온재 (ISO-PINK)	1 × 2 × 50T	30	SH	25,000	750,000
	! DOOR (점검구외)	500W × 600L	10	SET	185,000	1,850,000
	! 부자재비 (PAKING 류외 5종)		1	LOT		500,000
	2) MANUFACTURING FEE					
	! 절단비		1	LOT		850,000
	! 밴딩비		1	LOT		800,000
	! 용접, 사상, 조립		25	M/D	150,000	3,750,000
5	CONVEYOR DRIVE EQ'					<u>₩ 21,956,000</u>
	∴ 제작시방					
	! CONVEYOR SPEED : 0~2M/MIN					
	! DRIVE EL. MOTER : 1750 RPM/min × 0.75KW					
	! GEAR REDUER MESH BELT					
	MAT'L : 304 STAINLESS STEEL					
	1) 원 부자재비					
	! DRIVE EL. MOTOR	0.75KW	1	SET		150,000
	! GEAR REDUCER	1/385	1	SET		450,000
	! CONVEYOR & 제품JIG	16M÷P150=107 × 2EA	214	EA	75,000	16,050,000
	! SPROCKET	23NT	4	EA	220,000	880,000
	! SHAFT	φ50 × 1350L	2	EA	238,000	476,000
	! 부자재비 (BEARING 외 4종)		1	LOT		500,000
	! TENSION EQ'		2		225,000	450,000

	品 名	規 格	數 量	單 位	單 價	金 額
	2) MANUFACURING FEE		20	M/D	150,000	3,000,000
6	SPRAY SYSTEM (수세1垠, 탕세1垠)		2	垠	10,100,000	<u>₩ 20,200,000</u>
	∴ 제작시방					
	! SPRAY SYSTEM					
	TYPE : VERTICAL					
	ELECTRIC MOTOR : 2P × 2HP					
	MAT'L : 316 STAINLESS					
	! SPRAY NOZZLE					
	SPRAY : 3.8MM DIANMETER					
	SPRAY Q'TY : 9.5LIT/MIN					
	SPRAY ANGLE : 60 DEGREE					
	NOZZLE TYPE : VEE JET (FULL CONE/FLAT)					
	MAT'L : 304 STAINLESS					
	! PIPING SYSTEM					
	SIZE : 25A ~ 40A					
	MAT'L : 304 STAINLESS					
	PUMP OUT LET에 온도계 및 압력계 부착					
	1) 원 부자재비					
	! PUMP	350ℓ/min	1	SET		2,850,000
	! NOZZLE	FULL CONE	50	EA	12,500	625,000
	! 자유 조인트	3/8 SS	50	EA	17,500	875,000
	! 부 자재비		1	LOT		500,000
	! PIPING (VALVE 외 12종)		1	LOT		1,200,000
	2) MANUFACTURING FEE		10	M/D	150,000	1,500,000
	PRESSURE : 20 PSI					
	PIPING : MAT'L : 304 STAINLESS STEEL					
	SIZE : 20A ~ 40A					
	CONTROL VALVE : 25A BALL					
	1) 원 부자재비					
	! AIR CONTROL UNIT 외		1	LOT		500,000
	! AIR NOZZLE		3	SET	100,000	300,000
	! PIPING		1	LOT		250,000
	2) MANUFACTURING FEE		10	M/D	150,000	1,500,000

	品 名	規 格	數 量	單 位	單 價	金 額
7	BLOW OFF SYSTEM ∴ 제작시방 ! AIR BLOW (공장 AIR 사용) AIR NOZZLE : TYPE : WIND JET PRESSURE : 20 PSI PIPING : MAT'L : 304 STAINLESS STEEL SIZE : 20A ~ 40A CONTROL VALVE : 25A BALL 1) 원 부자재비 ! AIR CONTROL UNIT 외 ! AIR NOZZLE ! PIPING 2) MANUFACTURING FEE	BY-PASS	1 5 2 10	LOT SET LOT M/D	 120,000 250,000 150,000	<u>₩ 3,100,000</u> 500,000 600,000 500,000 1,500,000
8	HOT BLOW OFF EQ' (DRY-OVEN) ! 온도 : 90℃ ! CAPA : 13KW 1) 원 부자재비 ! AIR TOOL 전기 HEATER ! 열풍 NOZZLE EQ' (SUS 304) ! HOT BLOW M/C ! 기타 부자재비 2) MANUFACTURING FEE	13KW 4.1 m³/min × 2000mmAq	2 8 2 1 15	SET SET SET LOT M/D	1,800,000 250,000 1,500,000 150,000	<u>₩ 11,100,000</u> 3,600,000 2,000,000 3,000,000 250,000 2,250,000
9	HEATING SYSTEM (열원 : 전기) 수세#1 , 탕세#1 ∴ 제작시방 ! THE HEATER CAPACITY IS AS FOLLOWS DEBONDELUBE 60 DEG.C – 1) HEATER TYPE : TUBE MAT'L : SUS 304 2) MANUFACTURING FEE	10KW	10 5	EA M/D	280,000 150,000	<u>₩ 3,550,000</u> 2,800,000 750,000
10	PIPING SYSTEM ∴ 제작시방 1) 원 부자재비		1	LOT		<u>₩ 10,200,000</u> 500,000

	品 名	規 格	數 量	單 位	單 價	金 額
11	! WATER SUPPLY MAT'L : SUS 304 SIZE : 20A ~ 40A		1	LOT		450,000
	! DRAIN LINE MAT'L : SUS 304 SIZE : 40A					
	TANK DRAIN V/V은 BALL V/V 부착					
	! Air By pass & Pipping		1	LOT		8,500,000
	2) MANUFACTURING FEE		5	M/D	150,000	750,000
	EXHAUST SYSTEM					<u>₩ 5,350,000</u>
	∴ 제작시방					
	! 장비의 입구와 출구쪽에 VENTILATION 장치를 설치함 VENT. TAN : VOLUME : 30m ³ /min × 120mmAq MAT'L 304 STAINLESS STEEL					
	! HOOD AND DUCT MAT'L : 304 STAINLESS STEEL					
	1) 원 부자재비					
	! EXHAUST FAN					
4-0	! HOOD AND DUCT		1	LOT		3,850,000
	2) MANUFACTURING FEE		10	M/D	150,000	1,500,000
	AUTO LOADER SYSTEM		2	LOT	20,000,000	₩ 40,000,000
	세척#1 UNLOADER / 피막 UNLOADER					
5-0	ROBOT SYSTEM		1	LOT		₩ 43,500,000
	RS80 (KAWASAKI) PART		1	SET		사 급
	로봇 BASE & DUCT 외		1	SET		3,500,000
	CC-LINK(상위제어반과 통신)		1	SET		1,500,000
	JAW 기종별 제작		1	SET		2,500,000
	서보핸드 UNIT		1	SET		20,000,000
	PLC 프로그램 및 배선작업		1	SET		7,000,000
	COOLER		1	SET		3,000,000
	1차 시운전비(국내)		1	SET		3,500,000
	안전 FENCE & 기타 부자재비		1	SET		2,500,000

	品 名	規 格	數 量	單 位	單 價	金 額
6-0	ELECTRICAL SYSTEM (전기장치)		1	LOT		₩ 58,377,400
	- MAIN POWER : 415V x 3Φ x 50Hz					
	- CONTROL POWER : DC 24V					
	1) 원 부자재비					
	- MAIN PANEL	2000 x 2400 x 500	1	EA		2,500,000
	- SUB PANEL		5	LOT	375,000	1,875,000
	- NAME PLATE	AL 1.5t 외	1	LOT		470,000
	- MAIN NFB	EBS403/250A	1	EA		450,000
	- ELB	EBS103/75A	2	EA	145,000	290,000
	- SUB NFB	ABS33C	14	EA	28,200	394,800
	- SUB NFB	ABS32C	4	EA	16,900	67,600
	- MC	MC32,MC22,MC12	20	EA	33,800	676,000
	- EOCR (SHCHNEIDER)	3DM2-WRDUH	16	EA	129,000	2,064,000
	- TRANS	3KVA	1	EA		300,800
	- SMPS	LN70-24	2	EA	70,500	141,000
	- RELAY	MY4N/110V	16	EA	4,200	67,200
	- NOISE FILTER	SN6H-CM	1	EA		47,000
	- PLC CPU	Q03UPVCPU	1	EA		92,100
	- PLC INPUT	QX41	4	EA	200,500	802,000
	- PLC OUTPUT	QY41P	4	EA	200,500	802,000
	- PLC POWER	Q61P	1	EA		148,500
	- PLC BASE	Q38B	1	EA		225,600
	- PLC통신카드	ETHERNET	1	EA		893,000
	- PLC통신카드	RS422/485	2	EA	488,800	977,600
	- LINK(CABLE포함)	INPUT/32점	4	SET	58,200	232,800
	- LINK(CABLE포함)	OUTPUT/32점	4	SET	263,200	1,052,800
	- TOWER LAMP	3단/DC24V	1	EA		92,100
	- TURN LIGHT	1단/DC24V	7	EA	39,400	275,800
	- TOUCH SCREEN	GOT2000, 12.1"	1	EA		1,692,000
	- PANEL AIRCON	AIRMAJOR	1	LOT		1,650,000
	- CT	400/5A	2	EA	8,400	16,800
	- PT	415/110V,50VA	1	EA		92,100
	- METER	V, A METER	1	LOT		48,800
	- PROX S/W	OMRON	1	LOT		2,500,000
	- PHOTOX S/W	OMRON	1	LOT		226,000
	- OP SWITCH	KH2022ER외	1	LOT		470,000

	品名	規格	數量	單位	單價	金額
	- INVERTER	FR-A840-1.5K	3	EA	480,000	1,440,000
	- 온도제어기	TZ4ST-24R	8	EA	82,000	656,000
	- 온도센서	CA,500mm	8	EA	42,000	336,000
	- 온도보상도선	CA2C x 1.0sq	1	LOT		752,000
	- 동력CABLE		1	LOT		2,500,000
	- DATA CABLE	20C x 0.5sq 외	1	LOT		2,500,000
	- BUS BAR 제작	Cu 25mm,5T	1	LOT		560,000
	- 기타부자재		1	LOT		1,500,000
	- DUCT		1	LOT		2,500,000
	- 전장설계		1	LOT		3,500,000
	- 프로그램		1	LOT		3,500,000
	- 터치스크린 작화		1	LOT		1,500,000
	- 전장조립		1	LOT		3,500,000
	- 기체배선공사		1	LOT		7,000,000
	- 시운전		1	LOT		5,000,000