

2. 인허가 件 (대기, 수질) , 3. A/C TOWER & 배기 DUCT(옥외) , 4. spare part

	品 名	規 格	數 量	單 位	單 價	金 額
1-0	Tempering System					
1	BODY SHELL					<u>₩ 37,112,500</u>
	! PLATE (SS 41)	4 × 8 × 5T	880	KG	1,700	1,496,000
	! PLATE (SS 41)	4 × 8 × 9T	420	KG	1,700	714,000
	! PLATE (SUS 304)	4 × 8 × 4T	3500	KG	5,100	17,850,000
	! ANGLE (SUS304)	50 × 50 × 6T	550	KG	5,300	2,915,000
	! ANGLE (SUS304)	75 × 75 × 9T	500	KG	5,300	2,650,000
	! CHANNEL (SS41)	100 × 50 × 5T	850	KG	1,750	1,487,500
	! 기타 부자재비		1	LOT		500,000
	! 기계 가공비		1	LOT		2,000,000
	! 제작 조립비		50	LOT	150,000	7,500,000
2	INSULATION					<u>₩ 6,796,300</u>
	! ROCK WOOL FELT	1000 × 400 × 50T	1	LOT	18,000	2,850,000
	! 기타 부자재비		1	LOT		250,000
	! 축로		1	LOT		650,000
	! COVER		1	LOT		3,046,300
3	HEATING SYSTEM					<u>₩ 10,382,500</u>
	! HEAT BLEMENT	HEATH 2.5KW	70	SET	85,000	5,950,000
	! LEAD TERMINAL	3P × 100A	6	SET	11,250	67,500
	! 석면전선	5.5SQ	1	LOT		350,000
	! HOLDER		1	LOT		315,000
	! LEAD COVER		3	SET	400,000	1,200,000
	! 기타 부자재비 (DUCT LINE 1 SET)					2,500,000
4	CIRCULATION FAN SYSTEM					<u>₩ 6,502,000</u>
	! IMPELLER (SUS 304)	350φ	3	EA	415,000	1,245,000
	! SHAFT (SUS 304)	20φ	3	SET	188,000	564,000
	! MOTOR	2HP × 6P	3	대	150,000	450,000
	! SHAFT & BEARING		3	SET	218,500	655,500
	! STAND		3	SET	312,500	937,500
	! 기타 부자재비					150,000
	! 기계 가공비					500,000
	! 조립비					2,000,000

	品 名	規 格	數 量	單 位	單 價	金 額
5	DOOR & COVER					<u>₩ 2,087,500</u>
	! DOOR		2	SET	306,250	612,500
	! DOOR COVER		2	SET	100,000	200,000
	! IN/OUT CURTAIN		2	SET	93,750	187,500
	! HANDEL외		2	SET	150,000	300,000
	! 기타 부자재비					100,000
	! 기계 가공비					250,000
	! 조립비					437,500
6	CONVEYOR & DRIVING SYSTEM					<u>₩ 27,885,000</u>
	! MESH BAR CONVEYOR	1300W	22	M	580,000	12,760,000
	! MAIN DRUN (R/COATING 270φ × 1200)		6	SET	700,000	4,200,000
	! MOTOR	2HP	1	대		230,000
	! REDUCER	1/300	1	SET		2,800,000
	! 입출구 STAND		2	SET	500,000	1,000,000
	! BEARING	다종	1	LOT		500,000
	! CON'V TENSION 장치		4	SET	350,000	1,400,000
	! MOTOR & REDUCER BED		1	SET		220,000
	! 입출구 FRAME		1	SET		550,000
	! BELT COVER		2	EA	112,500	225,000
	! 기타 부자재비		1	LOT		500,000
	! 기계 가공비		1	LOT		1,500,000
	! 제작 조립비		1	LOT		2,000,000
2-0	Top Conveyor System(Out Con'V)		1	LOT		10,000,000
3-0	Tem'p In/Out Autoloader System		2	LOT	15,000,000	30,000,000
4-0	CONTROL SYSTEM					<u>₩ 38,357,000</u>
	MAIN PANEL	1600x1900x500	1	SET		2,100,000
	NFB BOX	400x700x200	1	SET		200,000
	OP PANEL	400x600x250	1	SET		200,000
	NAME PLATE	AL 1.0t 외...	1	SET		200,000
	MAIN ELB	EBS203/250A	1	SET		600,000
	HEATER ELB	EBS103/100A	2	SET	82,000	164,000
	SUB NFB	BKM33/20A	6	SET	45,000	270,000
	SUB NFB	BKM32/20A	2	SET	45,000	90,000
	MC	GMS-22/220V	2	SET	80,000	160,000

	品 名	規 格	數 量	單 位	單 價	金 額
	MC	GMS-12/220V	6	SET	60,000	360,000
	SMPS	DC24V,2A	1	SET	250,000	250,000
	TRANSE	AC480/220V,복권1kw	2	SET	320,000	640,000
	CP	2P/5A,보조접점형	6	SET	38,000	55,000
	NOISE FILTER	SN6H-CM	1	SET		15,000
	PLC CPU	SIEMENS	1	SET		1,700,000
	PLC INPUT	SIEMENS	4	SET	315,000	1,500,000
	PLC OUTPUT	SIEMENS	3	SET	420,000	1,500,000
	PLC POWER	SIEMENS	1	SET		450,000
	PLC 통신		1	SET		1,200,000
	PLC BASE	SIEMENS	1	SET		275,000
	LINK(CABLE포함)	INPUT/32점	3	SET	92,000	320,000
	LINK(CABLE포함)	OUTPUT/32점	2	SET	260,000	285,000
	TOWER LAMP	3단/DC24V	1	SET		98,000
	BUZZER	DC24V	1	SET		60,000
	OP SWITCH	KH2022ER외...	1	SET		100,000
	근접센서(콘넥터용)		10	SET		600,000
	PHOTO SENSOR	BPS3M-TDT	4	SET		480,000
	INVERTER	SIEMENS	1	SET		920,000
	TOUCH SCREEN	12"(작화포함)	1	SET		3,750,000
	COOLER	500kcal	1	SET		1,800,000
	SCR UNIT	STR-40kw	2	SET	640,000	1,280,000
	적산전력계	2CT	1	SET		160,000
	온도제어기	TZ42T-14R	2	SET	150,000	300,000
	온도센서	CA,300mm	3	SET	135,000	405,000
	BUS BAR제작	20mm,5t	1	SET		350,000
	온도보상도선	CA2Cx1.0sq	1	SET		120,000
	동력 CABLE ,HEATER CABLE		1	SET		2,500,000
	DATA CABLE	20Cx0.5sq 외..	1	SET		400,000
	기타부자재비	B BOX, PIPE배관. 잡자재	1	LOT		1,500,000
	설계 & 프로그램		1	LOT		3,000,000
	PANEL 전장조립		1	LOT		3,000,000
	기체배선 및 시운전		1	LOT		5,000,000