

見 積 書

西紀 2024 年 09 月 29日

HYUNDAI
WIA 현대위아 (주) 貴下

TPS Korea

납 기 : 계약 후 12 개월

대 표 : 윤 준 석



견적유효기간 : 발행 후 30 일

광주시 광산구 하남산단 8번로 127-15 (안청동)

지불조건 : 현대위아 결제 지불조건

TEL : (062) 958-4571

견적금액 : 칠억삼천구백만원整

(V.A.T. 별도)

FAX : (062) 958-4567

PROJECT 명 : WIA-India D/Shaft Grooving 9-2단계 증량투자

단위 : 원

No.	항 목	수량	단위	단 가	공급가액	비 고
1	D/Shaft Grooving_9-2단계	1	식	739,000,000	739,000,000	CNC 2대
2						
3						
4						
5						
6						
7						
8						
9						
10						
11						
12						
13						
14						
15						
16						
17						
18						
합 계		1	식		739,000,000	India

※ NOTE

1, 9-2단계 증량 프로젝트

Quotation Break Down Sheet

Project Name : WIA-India D/Shaft Grooving 9-2단계 증량투자 Project

Drive Shaft Grooving & Deburring (CNC Lathe)

Unit : Won

			Price			
Item			Q'ty	Unit	Total	Remarks
1	Base Machine	1) Machine Improvement CNC Lathe (SE2600L)	2	3,500,000	7,000,000	Supply by Hyundai-WIA
		2) Auto Door Improvement for Load/Unloading	2	2,500,000	5,000,000	Machine Added Equipment
		3) Clamping Face Driver with Center (Disk Type)	2	6,000,000	12,000,000	
		4) Sliding Cover Instead of Turret Space	2	1,500,000	3,000,000	
		5) Air Condition Installation	2	2,500,000	5,000,000	
		6) Pre-Locator for Drive Shaft	2	2,000,000	4,000,000	
		7) Call Light Flicker Signal Lamp (Q-Light)	2	300,000	600,000	
		8) Hydraulic Tank Unit for D-Shaft	2	5,000,000	10,000,000	
		9) Mist Collector Installation	2	7,000,000	14,000,000	
		10) Vortex Cooling Unit for D-Shaft	2	2,000,000	4,000,000	
		11) Individual Coolant System for CNC Lathe	2	21,000,000	42,000,000	with Chip Conveyor
2	Common Items	1) Gantry Loader for Drive Shaft (Funac-PLC)	2	131,000,000	262,000,000	Part Transportation Automation
		2) Work Piece Measuring Station for D-Shaft	1	31,000,000	31,000,000	
		3) Out-put Station with Stocker for D-Shaft	1	18,000,000	18,000,000	
		4) In-put Station with Rotation for D-Shaft	1	13,000,000	13,000,000	
		5) PP Loader of In-put Station for D-Shaft	1	9,000,000	9,000,000	
		6) PP Loader of Out-put Station for D-Shaft	1	10,000,000	10,000,000	
		7) Length Measuring for Model detection	1	5,000,000	5,000,000	
		8) Idle Conveyor	1	5,000,000	5,000,000	
		9) Deburring Tools (6x5x2)	50	300,000	15,000,000	Cutting Tooling
		10) Durable Tools-Holder (2x5x2)_1.6, 1.8	10	200,000	2,000,000	
		11) Perishable Tools-Insert (2x30x2)	120	40,000	4,800,000	
		12) Machine Interface for Automation of CNC Lathe	2	4,000,000	8,000,000	Electric Interface
		13) General & Documentation	2	3,000,000	6,000,000	Miscellaneous
		14) Chip Box, Mist Hood, Duct, Hose, Center	2	4,000,000	8,000,000	Anchoring
		15) Anchor Bolt & Block for Machine Installation	2	1,000,000	2,000,000	
3	Packing & Loading Cost for Transportation		2	23,500,000	47,000,000	at TPS Korea
Material Cost Sub Total				-	552,400,000	-
4	Labor Cost	1) Design	25	560,000	14,000,000	Design
		2) Assembly, Pre-acceptance	65	560,000	36,400,000	Assembly at TPS Korea
		3) Installation, Cutting Try-out	90	560,000	50,400,000	at WIA India Plant
		4) Training & Interpretation	6	560,000	3,360,000	
		5) Mass Production Support	16	560,000	8,960,000	
		6) Business trip expenses	1		28,700,000	
Labor Cost Sub Total			-	-	141,820,000	-
5	Supervisor Air Tansportation Charge		4	2,500,000	10,000,000	Korea ↔ India
Sub Total (1+2+3+4+5)			1	-	704,220,000	-
6	Sales & General Administration		5%		34,211,000	Administration
7	Margin & Profit				0	
Sub Total			-	-	34,300,000	-
Grand Total			1	-	739,000,000	9-2 단계